


R.D. WOOD COMMERCIAL COMMUNITY UNIT PLAN DP-343



GENERAL PROVISIONS:

- Total Land Area: 643,655 ± sq. ft. or 14.78 ± acres
Net Land Area: 546,440 ± sq. ft. or 12.54 ± acres
- Total Gross Floor Area: 210,369 sq. ft.
Total Net Floor Area Ratio: 32.6 percent
- Parking shall be provided in accordance with Section IV of the Unified Zoning Code, unless otherwise specified in the parcel description.
- Setbacks are as indicated on the C.U.P. drawing, or as specified in the parcel descriptions. If contiguous parcels are to be developed under the same ownership, setbacks between those parcels will not be required.
- A Drainage Plan shall be submitted to the appropriate Engineer for approval during the platting process. Required guarantees or drainage shall be provided at the time of platting improvements.
- Development of the RD Wood Commercial Community Unit Plan shall be contingent upon the platting of the subject property. The applicant shall provide four copies of an updated C.U.P. following the plat. Guarantees for pedestrian crossings, left-turn lanes, center lanes and right-turn decel lanes to all full movement approaches, and other specific street improvements for 135th St W. shall be further reviewed and determined at the time of platting.
- Signs will be as allowed by the Sign Code of the appropriate jurisdiction, with the following additional conditions/limitations:
 - Each parcel is permitted at least one freestanding sign with the following area restrictions:
Parcel 1: 150 sq. ft. of signage along 135th Street W.
Parcel 2: 150 sq. ft. of signage along 135th Street W.
Parcel 3: 50 sq. ft. of signage along 135th Street W.
 - As the frontage develops along the arterial roadways, monument type signs shall be spaced a minimum of 150' apart, irrespective of how land is leased or sold and share similar elements in design.
 - Flashing signs, rotating or moving signs, signs with moving lights or signs which create illusions of movement are not permitted.
 - Portable, billboards and off-site signs are not permitted.
 - Window display signs are limited to 25% of the window area.
 - No signs shall be allowed on the south, east, or north elevations of any building adjacent to residential zoning.
 - All freestanding signs must be monument type and shall have a maximum height of 15 feet for Parcels 1-3.
- Access Controls shall be as shown on the final plat.
- All exterior lighting shall be shielded to direct light disbursement in a downward direction.
- All parcels shall share similar or consistent parking lot lighting elements (i.e., fixtures, poles, and lamps, etc.).
 - Limited height of light poles, including fixtures, lamps and base, to 24 feet, except within 200 feet of residential zoning said lighting shall be a maximum height of 15 feet.
 - Extensive use of back lit canopies and neon or fluorescent tube lighting on buildings is not permitted.
- Utilities shall be installed underground on all parcels.
- Landscaping for this site shall be required as follows:
 - Development of all parcels within the C.U.P. shall comply with the landscaping requirements of the appropriate jurisdiction, with a shared palette of landscape materials among parcels. All unpaved areas shall be landscaped.
 - A landscape plan shall be prepared by a Kansas Landscape Architect for the above referenced landscaping, indicating the type, location, and specifications of all plant material. This plan shall be submitted to the Planning Department for their review and approval prior to issuance of a building permit.
 - A financial guarantee for the plant material approved on the landscape plan for that portion of the C.U.P. being developed shall be required prior to issuance of any occupancy permit, if the required landscape has not been planted.
 - A 15-foot landscaped yard shall be provided along the north, south, and east property lines of Parcel 3, and along the west line of Parcel 3 where abutting 135th Street West. The landscaped yard along the south property line may be located in Reserve A. The landscaped yard shall be planted with a landscaped earth berm containing one tree every 20 feet, with at least one-half of the trees being evergreen.
- Screening:
 - A six (6) to eight (8) foot high concrete/masonry wall shall be constructed along the north property line of Parcel 1 where adjacent to residential zoning. Said wall shall be constructed at the time any portion of Parcels 1 and 2 are developed.
 - This solid wall shall be constructed of a pattern and color that is consistent or compatible with the building walls.
 - Screening along the north, east, and south property lines of Parcel 3 shall be a combination of landscaping, wrought-iron or similar decorative fencing, and storage building walls.
- Rooftop mechanical equipment shall be screened from ground level view with similar materials to the main building per Unified Zoning Code.
- Trash receptacles, loading docks, outdoor storage, and loading areas shall be appropriately screened, with similar materials to the main building, to reasonably hide them from ground view.
- All buildings within Parcels 1 and 2, and Parcel 3 separately, of the C.U.P. shall share uniform architectural character, color, texture, and the same predominate exterior building material, as determined by the Director of Planning. Building walls and roofs must have predominately earth-tone colors, with vivid colors limited to incidental accent, and must employ materials similar to surrounding residential areas.
In lieu of the masonry wall requirement, the north, south, and east elevations of the perimeter storage buildings within Parcel 3 may be commercial metal siding over steel frame construction. In addition to the outward-facing north, south, and east elevations of the perimeter buildings within Parcel 3, the two most southeastern units (Building F and G) shall provide a combination of commercial metal siding and partial brick veneer on their south and east elevations, as indicated on the attached elevations. Interior buildings may be all metal with consistent colors and material to match the perimeter buildings. The office and climate-controlled building (Building H) shall have pitched roofs with composite (or similar) roofing materials and residential siding, as indicated on the attached elevations, with the balance of the buildings providing pitched roofs, which may consist of commercial metal roofing. The architectural design of the storage buildings in Parcel 3 shall be consistent with the architectural renderings reviewed and approved by the Planning Commission.
- Fire lanes shall be in accordance with the appropriate Fire Code. No parking shall be allowed in said fire lanes, although they may be used for passenger loading and unloading. The Fire Chief or his designated representative shall review and approve the location and design of all fire lanes. Fire hydrant installation and paved access to all building sites shall be provided for each phase of construction prior to the issuance of building permits.
- No parcel within this C.U.P. shall allow the use of adult entertainment establishments; sexually oriented business; correctional placement residences; night club in the city; night club in the county; and tavern and drinking establishment. Restaurants that serve liquor can be developed and may serve liquor, as long as food is the primary service of the establishment. Except for those associated with the self-storage warehouse use within Parcel 3, no overhead doors shall be allowed within 200 feet of residential zoning and shall not be facing any residential zoning district. Exterior audio systems that project sound beyond the boundaries of the C.U.P. are prohibited.
- Cross-lot circulation agreements shall be required at the time of platting to assure internal vehicular movement between Parcels 1 and 2.
- Amendments, adjustments or interpretations to this C.U.P. shall be done in accordance with the Unified Zoning Code.
- The Transfer of title of all or any portion of land included within the Community Unit Plan (or any amendments thereto) does not constitute a termination of the plan or any portion thereof, but said plan shall run with the land and be binding upon present owners, their successors and assigns.
- The development of this property shall proceed in accordance with the development plan as recommended for approval by the Planning Commission and approved by the Governing Body, and any substantial deviation of the plan, as determined by the Zoning Administrator and the Director of Planning, shall constitute a violation of the building permit authorizing construction of the proposed development.
- Any major changes in this development plan shall be submitted to the Planning Commission and to the Governing Body for their consideration.
- A plan for a pedestrian walk system shall be submitted and approved by the Director of Planning prior to the issuance of building permits. Said walk system shall link sidewalks along 135th St W. with the proposed buildings within Parcels 1 and 2, and to the office within Parcel 3.
- Approval of a site circulation plan by the Planning Director is required for each phase of construction prior to the issuance of a building permit. An overall site plan shall be required for review and approval by the Planning Director prior to the issuance of any building permits; the site plan shall ensure internal circulation within the parcels and joint use of ingress/egress openings and that private drive openings are not impacted/blocked by the layout of parking stalls or landscaping.
- The applicant shall record a CUP certificate with the Register of Deeds indicating that this tract (referenced as DP-343 R.D. Wood Commercial CUP) has special conditions for development on the property. A copy of the recorded certificate along with four copies of the approved CUP shall be submitted to the Metropolitan Area Planning Department within 60 days of recording the plat for the subject property, or the request shall be considered denied and closed.

PARCEL 1

A. Net Area: 82,700 sq. ft. or 1.90 acres
B. Maximum Building Coverage: 24,810 sq. ft. or 30 percent
C. Maximum Gross Floor Area: 28,945 sq. ft.
D. Floor Area Ratio: 35 percent
E. Maximum Number of Buildings: Two (2)
F. Maximum building height to conform to Chapter 28.08 Code of the City of Wichita, but shall be not greater than 35 feet.
G. Setbacks: See Drawing
H. Access Points: See Drawing
I. Permitted Uses: All permitted uses in the "NR" Neighborhood Retail zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #18.

PARCEL 2

A. Net Area: 82,700 sq. ft. or 1.90 acres
B. Maximum Building Coverage: 24,810 sq. ft. or 30 percent
C. Maximum Gross Floor Area: 28,945 sq. ft.
D. Floor Area Ratio: 35 percent
E. Maximum Number of Buildings: Two (2)
F. Maximum building height to conform to Chapter 28.08 Code of the City of Wichita, but shall be not greater than 35 feet.
G. Setbacks: See Drawing
H. Access Points: See Drawing
I. Permitted Uses: All permitted uses in the "NR" Neighborhood Retail zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #18.

PARCEL 3

A. Net Area: 382,300 sq. ft. or 8.78 acres
B. Maximum Building Coverage: 152,920 sq. ft. or 40 percent
C. Maximum Gross Floor Area: 152,920 sq. ft.
D. Floor Area Ratio: 40 percent
E. Maximum Number of Buildings: Twenty (20)
F. Maximum building height to conform to Chapter 28.08 Code of the City of Wichita, but shall be not greater than 35 feet.
G. Setbacks: See Drawing
H. Access Points: See Drawing
I. Permitted Uses: All permitted uses in the "GO" General Office zoning district of the Wichita-Sedgwick County Unified Zoning Code, including self-storage warehouse as restricted by Section III.D.6.y and any waivers as approved by the Governing Body, and except for those listed under G.P. #18.

RESERVE A

A. Net Area: 42,215 sq. ft. or 0.97 acres
B. Permitted Uses: Landscaping, lakes, open space, berms, sidewalks, drainage purposes, and utilities as confined to easements.

RESERVE B

A. Net Area: 55,000 sq. ft. or 1.26 acres
B. Permitted Uses: Landscaping, lakes, open space, berms, sidewalks, drainage purposes, and utilities as confined to easements.

REVISIONS

Submitted: April 10, 2017
Revised per staff comments: May 3, 2017
Revised per MAPC: May 18, 2017
Revised per CAB #3: June 5, 2017
Approved per County Commission: July 5, 2017
Revised per Adjustment (CUP2019-30): August 13, 2019
Revised per Amendment #1: March 11, 2022
Revised per Amendment #2: June 7, 2022

LEGAL DESCRIPTION:

All lots and blocks, R.D. Wood Commercial Addition, Wichita, Sedgwick County, Kansas; TOGETHER WITH that part of the Southwest Quarter of Section 12, Township 27 South, Range 2 West of the Sixth Principal Meridian, Sedgwick County, Kansas described as beginning at the northern most northeast corner of Lot 1, Block A, R.D. Wood Commercial Addition, Wichita, Sedgwick County, Kansas; thence N88°17'27"E coincident with the easterly extension of the north line of Lot 1 in said Block A, 250.00 feet to the northerly extension of the east line of Reserve "B" in said R.D. Wood Commercial Addition; thence S01°09'17"W coincident with the northerly extension of the east line of said Reserve "B", 496.00 feet to the northeast corner of said Reserve "B"; thence S88°17'27"W coincident with the north line of said Reserve "B", 250.00 feet to the northwest corner of said Reserve "B" and to a point in the east line of Lot 1 in said Block A; thence N01°09'17"E coincident with the east line of Lot 1 in said Block A, 496.00 feet to the point of beginning.

APPROVED CUP
DATE: 5-5-2022
BY: *Cherie Kroll*

DP-343
R.D. WOOD COMMERCIAL
COMMUNITY UNIT PLAN




SCALE: 1" = 60'

Baughman Company, P.A.
315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0148
ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

R.D. WOOD COMMERCIAL COMMUNITY UNIT PLAN DP-343

GENERAL PROVISIONS:

- Total Land Area: 520,704 ± sq.ft. or 11.95 ± acres
Net Land Area: 423,700 ± sq.ft. or 9.73 ± acres
- Total Gross Floor Area: 161,210 sq.ft.
Total Net Floor Area Ratio: 31 percent
- Parking shall be provided in accordance with Section IV of the Unified Zoning Code, unless otherwise specified in the parcel description.
- Setbacks are as indicated on the C.U.P. drawing, or as specified in the parcel descriptions. If contiguous parcels are to be developed under the same ownership, setbacks between those parcels will not be required.
- A Drainage Plan shall be submitted to the appropriate Engineer for approval during the platting process. Required guarantees or drainage shall be provided at the time of platting improvements.
- Development of the R.D. Wood Commercial Community Unit Plan shall be contingent upon the platting of the subject property. The applicant shall provide four copies of an updated C.U.P. following the plat. Guarantees for pedestrian crossings, left-turn lanes, center lanes and right-turn deceleration lanes to all full movement approaches, and other specific street improvements for 135th St W shall be further reviewed and determined at the time of platting.
- Signs will be as allowed by the Sign Code of the appropriate jurisdiction, with the following additional conditions/limitations:
 - Each parcel is permitted at least one freestanding sign with the following area restrictions:
Parcel 1: 150 sq. ft. of signage along 135th Street W.
Parcel 2: 150 sq. ft. of signage along 135th Street W.
Parcel 3: 50 sq. ft. of signage along 135th Street W.
 - As the frontage develops along the arterial roadways, monument type signs shall be spaced a minimum of 150' apart, irrespective of how land is leased or sold and share similar elements in design.
 - Flashing signs, rotating or moving signs, signs with moving lights or signs which create illusions of movement are not permitted.
 - Portable, billboards and off-site signs are not permitted.
 - Window display signs are limited to 25% of the window area.
 - No signs shall be allowed on the south, east, or north elevations of any building adjacent to residential zoning.
 - All freestanding signs must be monument type and shall have a maximum height of 15 feet for Parcels 1-3.
- Access Controls shall be as shown on the final plat.
- All exterior lighting shall be shielded to direct light disbursement in a downward direction.
- All parcels shall share similar or consistent parking lot lighting elements (i.e., fixtures, poles, and lamps, etc.).
 - Limited height of light poles, including fixtures, lamps and base, to 24 feet, except within 200 feet of residential zoning said lighting shall be a maximum height of 15 feet.
 - Extensive use of back lit canopies and neon or fluorescent tube lighting on buildings is not permitted.
- Utilities shall be installed underground on all parcels.
- Landscaping for this site shall be required as follows:
 - Development of all parcels within the C.U.P. shall comply with the landscaping requirements of the appropriate jurisdiction, with a shared palette of landscape materials among parcels. All unpaved areas shall be landscaped.
 - A landscape plan shall be prepared by a Kansas Landscape Architect for the above referenced landscaping, indicating the type, location, and specifications of all plant material. This plan shall be submitted to the Planning Department for their review and approval prior to issuance of a building permit.
 - A financial guarantee for the plant material approved on the landscape plan for that portion of the C.U.P. being developed shall be required prior to issuance of any occupancy permit, if the required landscape has not been planted.
 - A 15-foot landscaped yard shall be provided along the north, south, and east property lines of Parcel 3, and along the west line of Parcel 3 where abutting 135th Street West. The landscaped yard along the south property line may be located in Reserve A. The landscaped yard shall be planted with a landscaped earth berm containing one tree every 20 feet, with at least one-half of the trees being evergreen.
- Screening:
 - A six (6) to eight (8) foot high concrete/masonry wall shall be constructed along the north property line of Parcel 1 where adjacent to residential zoning. Said wall shall be constructed at the time any portion of Parcels 1 and 2 are developed.
 - This solid wall shall be constructed of a pattern and color that is consistent or compatible with the building walls.
 - Screening along the north, east, and south property lines of Parcel 3 shall be a combination of landscaping, wrought-iron or similar decorative fencing, and storage building walls.
- Rooftop mechanical equipment shall be screened from ground level view with similar materials to the main building per Unified Zoning Code.
- Trash receptacles, loading docks, outdoor storage, and loading areas shall be appropriately screened, with similar materials to the main building, to reasonably hide them from ground view.
- All buildings within Parcels 1 and 2, and Parcel 3 separately, of the CUP, shall share a uniform architectural character, color, texture and the same predominate exterior building material, as determined by the Director of Planning. Building walls and roofs must have predominately earth-tone colors, with vivid colors limited to incidental accent, and must employ materials similar to surrounding residential area.
In lieu of the masonry wall requirement, the north, south, and east elevation of the perimeter storage buildings within Parcel 3 may be commercial metal siding over steel frame construction. In addition to the outward-facing north, south and east elevation of the perimeter buildings within Parcel 3, the two most southeastern units (Buildings F and G) shall provide a combination of commercial metal siding and partial brick veneer on their south and east elevations, as indicated on the attached elevations. Interior buildings may be all metal with consistent colors and material to match the perimeter buildings. The office and climate-controlled building (Building H) shall have pitched roofs with composite (or similar) roofing materials and residential siding, as indicated on the attached elevations, with the balance of the buildings providing pitched roofs, which may consist of commercial metal roofing. The architectural design of the storage buildings in Parcel 3 shall be consistent with architectural elevations submitted by the applicant as part of this administrative adjustment CUP2019-00030.
- Fire lanes shall be in accordance with the appropriate Fire Code. No parking shall be allowed in said fire lanes, although they may be used for passenger loading and unloading. The Fire Chief or his designated representative shall review and approve the location and design of all fire lanes. Fire hydrant installation and paved access to all building sites shall be provided for each phase of construction prior to the issuance of building permits.
- No parcel within this C.U.P. shall allow the use of adult entertainment establishments; sexually oriented business; correctional placement residences; night club in the city; night club in the county; and tavern and drinking establishment. Restaurants that serve liquor can be developed and may serve liquor, as long as food is the primary service of the establishment. Except for those associated with the self-storage warehouse use within Parcel 3, no overhead doors shall be allowed within 200 feet of residential zoning and shall not be facing any residential zoning district. Exterior audio systems that project sound beyond the boundaries of the C.U.P. are prohibited.
- Cross-lot circulation agreements shall be required at the time of platting to assure internal vehicular movement between Parcels 1 and 2.
- Amendments, adjustments or interpretations to this C.U.P. shall be done in accordance with the Unified Zoning Code.
- The Transfer of title of all or any portion of land included within the Community Unit Plan (or any amendments thereto) does not constitute a termination of the plan or any portion thereof, but said plan shall run with the land and be binding upon present owners, their successors and assigns.
- The development of this property shall proceed in accordance with the development plan as recommended for approval by the Planning Commission and approved by the Governing Body, and any substantial deviation of the plan, as determined by the Zoning Administrator and the Director of Planning, shall constitute a violation of the building permit authorizing construction of the proposed development.
- Any major changes in this development plan shall be submitted to the Planning Commission and to the Governing Body for their consideration.
- A plan for a pedestrian walk system shall be submitted and approved by the Director of Planning prior to the issuance of building permits. Said walk system shall link sidewalks along 135th St W with the proposed buildings within Parcels 1 and 2, and to the office within Parcel 3.
- Approval of a site circulation plan by the Planning Director is required for each phase of construction prior to the issuance of a building permit. An overall site plan shall be required for review and approval by the Planning Director prior to the issuance of any building permits; the site plan shall ensure internal circulation within the parcels and joint use of ingress/egress openings and that private drive openings are not impacted/blocked by the layout of parking stalls or landscaping.
- The applicant shall record a CUP certificate with the Register of Deeds indicating that this tract (referenced as DP-343 R.D. Wood Commercial CUP) has special conditions for development on the property. A copy of the recorded certificate along with four copies of the approved CUP shall be submitted to the Metropolitan Area Planning Department within 60 days of recording the plan for the subject property, or the request shall be considered denied and void.



PARCEL 1

A. Net Area: 82,700 sq.ft. or 1.90 acres
 B. Maximum Building Coverage: 24,810 sq.ft. or 30 percent
 C. Maximum Gross Floor Area: 28,945 sq.ft.
 D. Floor Area Ratio: 35 percent
 E. Maximum Number of Buildings: Two (2)
 F. Maximum building height to conform to Chapter 28.08 Code of the City of Wichita, but shall be not greater than 35 feet.
 G. Setbacks: See Drawing
 H. Access Points: See Drawing
 I. Permitted Uses: All permitted uses in the "NR" Neighborhood Retail zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #18.

PARCEL 2

A. Net Area: 82,700 sq.ft. or 1.90 acres
 B. Maximum Building Coverage: 24,810 sq.ft. or 30 percent
 C. Maximum Gross Floor Area: 28,945 sq.ft.
 D. Floor Area Ratio: 35 percent
 E. Maximum Number of Buildings: Two (2)
 F. Maximum building height to conform to Chapter 28.08 Code of the City of Wichita, but shall be not greater than 35 feet.
 G. Setbacks: See Drawing
 H. Access Points: See Drawing
 I. Permitted Uses: All permitted uses in the "NR" Neighborhood Retail zoning district of the Wichita-Sedgwick County Unified Zoning Code, except for those listed under G.P. #18.

PARCEL 3

A. Net Area: 259,800 sq.ft. or 5.93 acres
 B. Maximum Building Coverage: 103,320 sq.ft. or 40 percent
 C. Maximum Gross Floor Area: 103,320 sq.ft.
 D. Floor Area Ratio: 40 percent
 E. Maximum Number of Buildings: Fifteen (15)
 F. Maximum building height to conform to Chapter 28.08 Code of the City of Wichita, but shall be not greater than 35 feet.
 G. Setbacks: See Drawing
 H. Access Points: See Drawing
 I. Permitted Uses: All permitted uses in the "GO" General Office zoning district of the Wichita-Sedgwick County Unified Zoning Code, including self-storage warehouse as restricted by Section III.D.6.y and any waivers as approved by the Governing Body, and except for those listed under G.P. #18.

RESERVE A

A. Net Area: 42,004 sq.ft. or 0.96 acres
 B. Permitted Uses: Landscaping, lakes, open space, berms, sidewalks, drainage purposes, and utilities as confined to easements.

RESERVE B

A. Net Area: 55,000 sq.ft. or 1.26 acres
 B. Permitted Uses: Landscaping, lakes, open space, berms, sidewalks, drainage purposes, and utilities as confined to easements.

REVISIONS

Submitted:	April 10, 2017
Revised per staff comments:	May 3, 2017
Revised per MAPC:	May 18, 2017
Revised per CAB #3:	June 5, 2017
Approved per County Commission:	July 5, 2017
Revised per Adm. Adj. CUP2019-30:	August 13, 2019

LEGAL DESCRIPTION:

A portion of the Southwest ¼ of Section 12, Township 27 South, Range 2 West of the 6th Principal Meridian, Sedgwick County, Kansas, more particularly described as follows: Beginning at a point 990 feet North and 50 feet East of the Southwest corner of said Southwest ¼; thence North parallel with the west line of said Southwest ¼ a distance of 766 feet, more or less; thence East parallel with the South line of said Southwest ¼ a distance of 800 feet; thence South parallel with the west line of said Southwest ¼ a distance of 496 feet, more or less; thence East parallel with the South line of said Southwest ¼ a distance of 250 feet; thence South parallel with the west line of said Southwest ¼ a distance of 270 feet, more or less; thence West parallel with the South line of said Southwest ¼ a distance of 850 feet, more or less, to the point of beginning.

APPROVED CUP
 MAPC 5-18-17
 Back 7-5
 As per AA CUP2019-30 plan
 MAPD Copy 204
DP-343
R.D. WOOD COMMERCIAL COMMUNITY UNIT PLAN
 Baughman Company, P.A.
 315 Ellis St. Wichita, KS 67211 P 316.262.7271 F 316.262.0149
 Baughman ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE
 SCALE: 1" = 60'



Wichita-Sedgwick County Metropolitan Area Planning Department

July 14, 2017

Russ Ewy
Baughman Company PA
315 Ellis
Wichita, KS 67211

RE: ZON2017-00018 and CUP2017-00016 – Zone change from SF-20 Single Family Residential to LC Limited Commercial and creation of the R.D. Wood Commercial Community Unit Plan CUP DP-343 on property located approximately 1,000 feet north of 13th Street North on the east side of 135th Street West.

Dear Mr. Ewy

At its regular meeting on **July 5, 2017**, the Board of Sedgwick County Commissioners considered the above captioned request. The action of the Board was to **APPROVE** the request.

The applicant shall record a CUP certificate with the Register of Deeds indicating that this tract (referenced as DP-343 R.D. Wood Commercial CUP) has special conditions for development on the property. A copy of the recorded certificate along with four copies of the approved CUP shall be submitted to the Metropolitan Area Planning Department within 60 days of recording the plat for the subject property, or the request shall be considered denied and closed.

If you have any questions concerning this application, please contact our office at 268-4421.

Sincerely,

Scott Knebel, AICP
Planning Manager

Copies to:

Ronald A. Goowdwin, Goodwin Properties LLC, 10300 W. Central Ave., Wichita, KS 67212
Vincent Wesolowsky, 13206 W. Hunters View, Wichita, KS 67235
Bill Smith, 13106 W. Nantucket, Wichita, KS 67235
Larry Wren, 13402 W. Hunters View, Wichita, KS 67235
Janice Dennis, 13314 W. Hunters View, Wichita, KS 67235
Ann Sanders, 13310 W. Hunters View, Wichita, KS 67235
Gerald Robbins, 13120 W. Hunters View, Wichita, KS 67235

~~City Hall • 10th Floor • 455 North Main • Wichita, Kansas 67202-1688~~

~~T 316.268.4421 F 316.268.4300~~

www.wichita.gov

RE: ZON2017-00018 and CUP2017-00016 – Zone change from SF-20 Single Family Residential to LC Limited Commercial and creation of the R.D. Wood Commercial Community Unit Plan CUP DP-343 on property located approximately 1,000 feet north of 13th Street North on the east side of 135th Street West

July 14 , 2017

Page 2

David Dennis, 3rd District, Board of County Commissioners
Justin Waggoner, County Counselor's Office
Jim Weber, Sedgwick County Public Works
Kelly Dixon, Metropolitan Area Building and Construction Department



Wichita-Sedgwick County Metropolitan Area Planning Department

August 13, 2019

R.D. Wood
3540 W. Douglas Ave., Suite 3
Wichita, KS 67203-5455

Baughman Company, P. A.
Attn: Russ Ewy
315 Ellis
Wichita, KS 67211

RE: CUP2019-30 – City Administrative Adjustment to Parcel 3 of the R.D. Wood Commercial CUP DP-343; generally located east of 135th Street West and north of 13th Street North.

Legal Description: Lot 1, Block A, R.D. Wood Commercial Addition

Dear Applicants:

We received and reviewed your request for an Administrative Adjustment to Parcel 3 of DP-343 to General Provision #16 as follows (revisions are bolded and underscored):

All buildings within Parcels 1 and 2, and Parcel 3 separately, of the CUP, shall share a uniform architectural character, color, texture and the same predominate exterior building material, as determined by the Director of Planning. Building walls and roofs must have predominately earth-tone colors, with vivid colors limited to incidental accent, and must employ materials similar to surrounding residential area.


In lieu of the masonry wall requirement, the north, south, and east elevation of the perimeter storage buildings within Parcel 3 **may be commercial metal siding over steel frame construction**. In addition to the outward-facing north, south and east elevation of the perimeter buildings within Parcel 3, the two most southeastern units **(Buildings F and G) shall provide a combination of commercial metal siding and partial brick veneer on their south and east elevations, as indicated on the attached elevations**. Interior buildings may be all metal with consistent colors and material to match the perimeter buildings. The office and climate-controlled building **(Building H)** shall have pitched roofs with composite (or similar) roofing materials **and residential siding, as indicated on the attached elevations**, with the balance of the buildings providing pitched roofs, which may consist of commercial metal roofing. **The architectural design of the storage buildings in Parcel 3 shall be consistent with architectural elevations submitted by the applicant as part of this administrative adjustment CUP2019-00030. (These elevations were agreed to by Applicant and Neighborhood at the District #3 Citizens Advisory Board Meeting.)**

On the basis of our review, we find that adjusting the CUP in the manner stated above is consistent with the approved CUP and will not have an adverse effect on the CUP or adjacent properties, nor will it be a substantial deviation of the original plan.

Our signatures below indicate that the CUP shall be adjusted as stated in this letter. This CUP adjustment shall not be deemed to alter any other provisions of the CUP except as expressly stated herein.


The "Development Application" sign should now be removed from the property. Please submit four (4) copies of the revised CUP drawing within 60 days in order for this adjustment to be considered final.


Dale Miller, Director
Metropolitan Area Planning Department



Scott Knebel, Zoning Administrator
Metropolitan Area Planning Department

cc: MABCD


Bryan Frye, CM District V
Cory Buchta, CSR District V




west elevation | 01



east elevation | 02



north elevation | 03



south elevation | 04

APPROVED

*elevation drawing DP-343
CVP2019-30
Date: Elmora 8-13-2019*

Copy 2 of 4
OFFICE



STUDIUM
151 N. Rock Island, Suite 1B
Wichita, Kansas 67202
studiumwichita.com 316.295.4563




Max Secure Storage
135th West & 13th St. North, Wichita, Kansas

Permit Set
02.12.19

A1.10



west elevation 102
 $\frac{3}{32}'' = 1'-0''$
 0 2 4 6 8



east elevation 104
 $\frac{3}{32}'' = 1'-0''$
 0 2 4 6 8

metal siding
 brick veneer
 wainscot



north elevation 103
 $\frac{3}{32}'' = 1'-0''$
 0 2 4 6 8



south elevation 105
 $\frac{3}{32}'' = 1'-0''$
 0 2 4 6 8

metal siding
 brick veneer
 wainscot

DOOR SCHEDULE BUILDING F				
DOOR COUNT	TYPE	WIDTH	HEIGHT	BRAND / LATCH
A 14	7 x 7 roll up	7'-0"	7'-0"	DBCI M650 / C-48755

Copy 2 of 4
 BLDG "F"

APPROVED

*elevation drawing DP-343
 CVP2019-30*

Date: 8-13-2019 Blaw


STUDIUM
 151 N. Rock Island, Suite 18
 Wichita, Kansas 67202
 studiumwichita.com 316.295.4563




Max Secure Storage
 135th West & 13th St. North, Wichita, Kansas

Permit Set
 02.12.19


A1.6




architectural plan building G | 01
 3/32" = 1'-0"
 0 2 4 6 8




north elevation | 02
 3/32" = 1'-0"
 0 2 4 6 8



east elevation | 03
 3/32" = 1'-0"
 0 2 4 6 8



south elevation | 04
 3/32" = 1'-0"
 0 2 4 6 8



west elevation | 05
 3/32" = 1'-0"
 0 2 4 6 8

DOOR SCHEDULE BUILDING G				
DOOR COUNT	TYPE	WIDTH/HEIGHT	BRAND	LAICH
A 1	17	10' x 10' (98 up, 10' 0" 10' 0")	DBCI M650	C-48755


Permit Set
 02.12.19

Copy 2 of 4
 BLDG "G"

APPROVED








elevation drawing DP-34B
 CVP 2019-30
 Date: 8-13-2019 Blm

STUDIUM
 151 N. Rock Island, Suite 1B
 Wichita, Kansas 67202
 studiumwichita.com 316.295.4563



Max Secure Storage
 135th West & 13th St. North, Wichita, Kansas

A1.7



OVERHEAD DOOR SCHEDULE BUILDING H					
DOOR COUNT	TYPE	WIDTH	HEIGHT	BRAND	LATCH
A	16	4' x 7' roll up	4'-0"	7'-0"	DBCI M450 C-48755
B	10	7' x 7' roll up	7'-0"	7'-0"	DBCI M450 C-48755
C	24	9' x 7' roll up	9'-0"	7'-0"	DBCI M450 C-48755

Copy 2 of 4
BLOG "H"

APPROVED

elevation drawing DP-343
CVP 2019-30
Date: 8-13-2019 *blm*



Max Secure Storage

135th West & 13th St. North, Wichita, Kansas

STUDIUM
151 N. Rock Island, Suite 1B
Wichita, Kansas 67202
studiumwichita.com 316.295.4563

Permit Set
02.12.19

A1.8