


WI 2441 Morgan 2




Scale 1:2829

0 50 100 150

Metres

Future Carriers



85' Foot Monopole

View from East


Equipment located on Rooftop




Building

14' 8"

Drawing Not to Scale



CENTER LINE WEBB RD




PROPERTY INFO

DESCRIBED AS:
THE WEST 325 FT and NORTH 300 FT OF
LOT 2 BLOCK 1 PARK MEADOWS ESTATES ADDITION
TO WICHITA, SEDGWICK CO., KANSAS

KEY No: C 411470003
PARCEL ID: 118280330104103
CONTROL No: 187113



T-MOBILE WIRELESS
WI 2441 MORGANZ



TO HARRY STREET
↓


or modify existing structures in order to meet the applicant's communication needs. The nearest available towers are located approximately a mile and one-half from that site. T-Mobile is already located on one of those towers and the other towers are too close to T-Mobile's existing site to enhance service in the target area the new tower is to serve.


2. The proposed wireless communication facility is compatible with the character of the area, which is developed with a variety of commercial uses along the Harry Street corridor and has significant buffers in the form of setbacks exceeding 200 feet from residential zoning; the tower is partially obscured by a building and will require no strobe lighting.
3. The proposed wireless communication facility minimizes the silhouette of the facility by its monopole design and uses materials and colors that minimize glare.

Based on compliance with the Location/Design Guidelines of the Wireless Communication Master Plan, our signatures below indicate that an Administrative Permit for a wireless communication facility is hereby GRANTED for the above-referenced property, subject to the following conditions:

1. All requirements of Section III.D.6.g. of the Unified Zoning Code shall be met.
2. The applicant shall obtain all permits necessary to construct the wireless communication facility, and the wireless communication facility shall be erected within one year of the issuance of this Administrative Permit.
3. The site shall be developed in general conformance with the approved site plan and elevation drawing. All improvements shall be completed before the facility becomes operational.
4. The support structure shall be a "monopole" design and shall be silver or gray or a similar unobtrusive color with a matte finish to minimize glare.
5. The monopole shall be 85 feet in height and shall be designed and constructed to accommodate communication equipment for at least three wireless service providers. If not prohibited otherwise, the tower shall be capable of extension up to 100 feet and provide for a total of four carriers.
6. The applicant shall obtain FAA approval regarding "objects affecting navigable airspace" and "impacts to terminal instrument procedures" for the proposed wireless communication facility and shall comply with all conditions of FAA approval. The applicant shall submit a copy of FAA approval to the MAPD, Office of Central Inspection, and Director of Airports prior to the issuance of a building permit.
7. The site shall be developed and operated in compliance with all federal, state, and local rules and regulations.
8. If the Zoning Administrator finds that there is a violation of any of the conditions of the Administrative Permit, the Zoning Administrator, in addition to enforcing the other remedies set forth in the Unified Zoning Code, may, with the concurrence of the Planning Director, declare that the Administrative Permit is null and void.

The "Development Application" sign should now be removed from the property.


John L. Schlegel
Planning Director


Kurt A. Schroeder
Superintendent of Central Inspection



Wichita-Sedgwick County Metropolitan Area Planning Department

July 26, 2005

Homer Morgan
2110 Industrial
Wichita, KS 67207

T-Mobile Wireless
Attention: George Wyrick
4533 Enterprise Dr.
Oklahoma City, OK 73128

Greg Ferris
P.O. Box 573
Wichita, KS 67201

Re: BZA2005-00036 – Administrative Permit for an 85-foot high wireless communication facility on property zoned “LC” Limited Commercial (1530 South Webb).

Revised Legal Description: The west 325 ft and north 300 ft of Lot 2, Block 1, Park Meadows Estates.

We have reviewed your request for an Administrative Permit for an 85-foot high monopole tower for use by T-Mobile Wireless on property zoned “LC” General Commercial. Section III.D.6.g.(3)(c) of the Wichita-Sedgwick County Unified Zoning Code states that new ground-mounted wireless communication facilities up to 85 feet in height in the “LC” Limited Commercial zoning district shall be approved by Administrative Permit if they conform to the Compatibility Height Standards of Section IV-C.5.b. of the Unified Zoning Code and the Location/Design Guidelines of the Wireless Communication Master Plan.

The Compatibility Height Standards require the proposed 85-foot high monopole to be located no closer than 85 feet from the lot line of property zoned “TF-3” Two-Family Residential or more restrictive. The proposed 85-foot high monopole, as shown on the site plan submitted with this application, is located greater than 100 feet from property zoned “TF-3” or more restrictive; therefore, we find that the request does conform to the Compatibility Height Standards.

In reviewing your request’s conformance to the Location/Design Guidelines of the Wireless Communication Master Plan, we find the following:

1. The applicant has demonstrated that there is no available space on existing or approved wireless communication facilities or other structures and there is no other feasible opportunity to rebuild