

MATCHLINE LS2

LANDSCAPE REQUIREMENTS

LANDSCAPE BUFFER REQUIREMENT (NORTH PROPERTY LINE)	
1 TREE PER 40 LF	
785 LF FRONTAGE / 40 = 20	
REQUIRED LANDSCAPE	PROVIDED LANDSCAPE
20 SHADE TREES OR 40 ORNAMENTAL TREES	41 ORNAMENTAL TREES
LANDSCAPE STREETYARD REQUIREMENT	
TOTAL LINEAR FEET OF STREET FRONTAGE = 1,698 FT.	
LESS THE GREATEST PERPENDICULAR DISTANCE = 423 FT.	
ADJUSTED STREET FRONTAGE = 1,275 FT.	
ADJUSTED STREET FRONTAGE * SF FACTOR = REQUIRED SF OF STREETYARD REQUIRED	
REQUIRED LANDSCAPE	PROVIDED LANDSCAPE
1,277 FT. * 20 = 25,540 SF	44,419 SF
52 TREES	63 TREES
PARKING LOT LANDSCAPE REQUIREMENTS	
1 TREE PER 20 SPACES	
419 TOTAL PARKING SPACES	
419 SPACES / 20 = 21	
REQUIRED LANDSCAPE	PROVIDED LANDSCAPE
21 SHADE TREES OR 42 ORNAMENTAL TREES	21 SHADE TREES

NOTE:
ENTIRE SITE SHALL BE IRRIGATED BY AN AUTOMATIC IRRIGATION SYSTEM. SYSTEM SHALL BE DESIGNED USING SEPARATE ZONES FOR LAWN AND SHRUBS. A RAIN SENSOR WILL BE INSTALLED TO HELP CONSERVE WATER.

PLANT MATERIAL SCHEDULE

QUANT.	COMMON NAME	BOTANICAL NAME	SIZE/REMARKS
22	URBANITE ASH	FRAXINUS PENNSYLVANICA 'URBANITE'	3" C.A.L.; 12'-14' HT.
38	ARISTOCRAT PEAR	PYRUS CALLERYANA 'ARISTOCRAT'	2" C.A.L.; 8'-10' HT.
43	'PRAIRIFIRE' CRABAPPLE	MALUS SPP. 'PRAIRIFIRE'	2" C.A.L.; 7'-8' HT.
21	HETZI COLUMN JUNIPER	JUNIPERUS CHINENSIS 'HETZI COLUMNARIS'	5 GALLON; 18" HT. MIN.
323	MINT JULEP JUNIPER	JUNIPERUS CHINENSIS 'MINT JULEP MONLEP'	5 GALLON; 18" HT. MIN.
8	MAIDEN GRASS	MISCANTHUS SINENSIS 'GRACILLIMUS'	5 GALLON
183	'ANTHONY WATERER' SPIRAEA	SPIRAEA X. BUMALDA 'ANTHONY WATERER'	2 GALLON
494	BROADMOOR JUNIPER	JUNIPERUS SABINA 'BROADMOOR'	1 GALLON
377	CRIMSON PYGMY BARBERRY	BERBERIS THUNBERGII 'ATROPURPUREA NANA'	1 GALLON
275	DWARF FOUNTAIN GRASS 'HAMELN'	PENNISETUM ALOPECUROIDES 'HAMELN'	1 GALLON
1089	STEEL BED EDGING (LF)	3/16" X 4" RYERSON OR APPROVED EQUAL	

SHOPS "A"
LOT 1

ALBERTSONS
LOT 1

RAPID
MUFFLER

DP-76
LANDSCAPE PLAN
APPROVED 3/6/97 BY DM

BED PREPARATION

ALL SHRUB AND GROUND COVER AREAS SHALL RECEIVE TWENTY-ONE (21) CUBIC FEET OF PINE BARK MULCH, NINE (9) CUBIC FEET OF AGED, STERILIZED COW MANURE, AND EIGHT (8) CUBIC FEET OF COARSE SAND PER 100 SQUARE FEET OF BED AREA. ROTO-TILL AMENDMENTS INTO SOIL TO A DEPTH OF EIGHT (8) INCHES.

MIX SIERRA 17-6-12 PLUS MINORS INTO THE TOP TWO (2) INCHES OF SOIL IN THE PLANTING BEDS AT A RATE OF FIVE (5) POUNDS PER 100 SQUARE FEET.

EACH TREE SHALL RECEIVE THREE (3) CUBIC FEET OF PINE BARK MULCH AND ONE (1) CUBIC FOOT OF AGED, STERILIZED COW MANURE. MIX WITH THE TOPSOIL AND USE AS A BACKFILL. APPLY FOUR (4) AGRIFORM TABLETS (20-10-5 PLUS MINORS, 21 GRAM) TO EACH TREE SMALLER THAN TWO INCHES IN CALIPER. APPLY SIX (6) AGRIFORM TABLETS (20-10-5 PLUS MINORS, 21 GRAM) TO EACH TREE HAVING A TRUNK TWO INCHES IN CALIPER OR LARGER. EACH PINE TREE SHALL RECEIVE FOUR (4) TABLETS PER TREE. EQUALLY SPACE TABLETS SIX (6) INCHES OUTSIDE THE BURLAP AND FOUR (4) INCHES BELOW FINISH GRADE.

MULCH

MULCH ALL PLANTING BEDS AND TREE WELLS WITH SHREDDED CYPRESS MULCH TO A DEPTH OF TWO INCHES.

LAWN

ALL AREAS INDICATED ON DRAWINGS AND AREAS DISTURBED BY CONSTRUCTION SHALL BE SODDED WITH SOLID SLAB HYBRID FESCUE SOD. WATER AND ROLL IN ACCORDANCE WITH STANDARD NURSERY PRACTICE.

SPRING: APPLY ULTIMATE GREEN 20-5-10 BY ZIPP INDUSTRIES AT A RATE OF FIVE (5) POUNDS PER 1,000 SQUARE FEET TO ALL LAWN AREAS.

FALL: APPLY 10-20-10 GRANULAR FERTILIZER AT A RATE OF FIVE (5) POUNDS PER 1,000 SQUARE FEET TO ALL LAWN AREAS.

GENERAL NOTES

CALL 1-800-344-7233 FOR INFORMATION ON THE LOCATION OF ALL UNDERGROUND UTILITIES. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE CAUSED TO UTILITIES (BOTH OVERHEAD AND BURIED) WHICH MAY BE ON THE PROJECT SITE DURING LANDSCAPE INSTALLATION. CONTRACTOR SHALL SEEK THE ASSISTANCE OF LOCAL UTILITIES AND THE OWNER IN LOCATING THE UTILITIES PRIOR TO PERFORMING TRENCHING OPERATIONS IN ANY AREA.

PLANT TREES THREE (3) INCHES ABOVE FINISHED GRADE. CUT TWINE FROM AROUND THE TRUNK AND PULL BACK THE BURLAP FROM THE TOP 1/3 OF THE ROOT BALL.

ALL TREES PLANTED IN THE PARKING ISLANDS SHALL HAVE A ROCK SUMP 30" IN DEPTH AND 8" IN DIAMETER. ROCK SHALL BE 3/4" - 1 1/2" IN SIZE AND WASHED. TOP OF SUMP SHALL BE COVERED WITH FILTER FABRIC.


PLANT SHRUBS TWO (2) INCHES ABOVE FINISHED GRADE. CROWN ISLANDS 6" ABOVE TOP OF CURB OR AS DIRECTED ON THE DRAWINGS.

ALL PLANTING BEDS SHALL HAVE POSITIVE DRAINAGE OUT OF THE PLANTING BEDS.

PLANT SPACING


HETZI COLUMN JUNIPER	42" O.C.
MINT JULEP JUNIPER	42" O.C.
MAIDEN GRASS	36" O.C.
BROADMOOR JUNIPER	30" O.C.
'ANTHONY WATERER' SPIRAEA	21" O.C.
DWARF FOUNTAIN GRASS 'HAMELN'	18" O.C.
CRIMSON PYGMY BARBERRY	15" O.C.

2/14/97 ISSUED FOR REVIEW		
NO.	DATE	DESCRIPTION
REVISIONS		
ALBERTSONS		
AMIDON & 21ST STREET NORTH WICHITA, KANSAS		
ALBERTSONS		
250 PARK CENTER BLVD.; BOX 20 BOISE, IDAHO 83726		
LANDSCAPE PLAN		
JOB NUMBER 27000033		PROTOTYPE
DESIGNED BY: DTA / AJR		STORE NUMBER
DRAWN BY: AJR		
APPROVED BY: DTA		
DATE: 2/14/97		
LANDSCAPE ARCHITECTS 2942 EAST 21ST ST. SUITE 225 TULSA, OK 74114 918-742-1463 FAX 918-742-1479		SHEET NUMBER LS101 of 2



COOLIDGE AVE.

AMIDON




LIQUOR STORE
LOT 2

LEGAL DESCRIPTION
Block 1, vacated 22nd Street between Amidon Avenue and Coolidge Avenue, and Lots 11 through 20, inclusive, in Block 2, all in Gardner's Riverlawn Addition to the City of Wichita, Sedgwick County, Kansas; EXCEPT beginning at the Southwest corner of Block 1, Gardner's Riverlawn Addition; thence east along the South line of said Block 1 a distance of 17 feet; thence northwesterly along a curve to the right having a radius of 17.63 feet to a point on the West line of said Block 1; thence south along said West line a distance of 17 feet to the point of beginning; AND EXCEPT the west 10 feet of the north 195 feet of Block 1, adjacent to Block 1 on the North, and the west 10 feet of Lot 20, Block 2.
Lots 1, 2, 3
Amidon Plaza Addition
Wichita, Sedgwick County, Kansas


LANDSCAPE PLAN

APPROVED 3/6/12 BY *[Signature]*



NOTE:
REFER TO SHEET LS-1 FOR LANDSCAPE PLANT MATERIALS SCHEDULE.

MATCHLINE LSI



BED PREPARATION

ALL SHRUB AND GROUND COVER AREAS SHALL RECEIVE TWENTY-ONE (21) CUBIC FEET OF PINE BARK MULCH, NINE (9) CUBIC FEET OF AGED, STERILIZED COW MANURE, AND EIGHT (8) CUBIC FEET OF COARSE SAND PER 100 SQUARE FEET OF BED AREA. ROTO-TILL AMENDMENTS INTO SOIL TO A DEPTH OF EIGHT (8) INCHES.
MIX SIERRA 17-6-12 PLUS MINORS INTO THE TOP TWO (2) INCHES OF SOIL IN THE PLANTING BEDS AT A RATE OF FIVE (5) POUNDS PER 100 SQUARE FEET.
EACH TREE SHALL RECEIVE THREE (3) CUBIC FEET OF PINE BARK MULCH AND ONE (1) CUBIC FOOT OF AGED, STERILIZED COW MANURE. MIX WITH THE TOPSOIL AND USE AS A BACKFILL. APPLY FOUR (4) AGRIFORM TABLETS (20-10-5 PLUS MINORS, 21 GRAM) TO EACH TREE SMALLER THAN TWO INCHES IN CALIPER. APPLY SIX (6) AGRIFORM TABLETS (20-10-5 PLUS MINORS, 21 GRAM) TO EACH TREE TWO INCHES TO FOUR INCHES IN CALIPER OR LARGER. EACH PINE TREE SHALL RECEIVE FIVE (5) TABLETS PER TREE. EQUALLY SPACE TABLETS SIX (6) INCHES OUTSIDE THE BURLAP AND FOUR (4) INCHES BELOW FINISH GRADE.

MULCH

MULCH ALL PLANTING BEDS AND TREE WELLS WITH SHREDDED CYPRESS MULCH TO A DEPTH OF TWO INCHES.

LAWN

ALL AREAS INDICATED ON DRAWINGS AND AREAS DISTURBED BY CONSTRUCTION SHALL BE SODED WITH SOLID SLAB HYBRID FESCUE SOD. WATER AND ROLL IN ACCORDANCE WITH STANDARD NURSERY PRACTICE.
SPRING: APPLY ULTIMATE GREEN 20-5-10 BY ZIPP INDUSTRIES AT A RATE OF FIVE (5) POUNDS PER 1,000 SQUARE FEET TO ALL LAWN AREAS.
FALL: APPLY 10-20-10 GRANULAR FERTILIZER AT A RATE OF FIVE (5) POUNDS PER 1,000 SQUARE FEET TO ALL LAWN AREAS.

GENERAL NOTES

CALL 1-800-344-7233 FOR INFORMATION ON THE LOCATION OF ALL UNDERGROUND UTILITIES.
CONTACT PRIOR TO DIGGING. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE CAUSED TO UTILITIES (BOTH OVERHEAD AND BURIED) WHICH MAY BE ON THE PROJECT SITE DURING LANDSCAPE INSTALLATION. CONTRACTOR SHALL SEEK THE ASSISTANCE OF LOCAL UTILITIES AND THE OWNER IN LOCATING THE UTILITIES PRIOR TO PERFORMING TRENCHING OPERATIONS IN ANY AREA.
PLANT TREES THREE (3) INCHES ABOVE FINISHED GRADE.
CUT TWINE FROM AROUND THE TRUNK AND PULL BACK THE BURLAP FROM THE TOP 1/3 OF THE ROOT BALL.
ALL TREES PLANTED IN THE PARKING ISLANDS SHALL HAVE A ROCK SUMP 30" IN DEPTH AND 8" IN DIAMETER. ROCK SHALL BE 3/4" - 1 1/2" IN SIZE AND WASHED. TOP OF SUMP SHALL BE COVERED WITH FILTER FABRIC.
PLANT SHRUBS TWO (2) INCHES ABOVE FINISHED GRADE.
CROWN ISLANDS 6" ABOVE TOP OF CURB OR AS DIRECTED ON THE DRAWINGS.
ALL PLANTING BEDS SHALL HAVE POSITIVE DRAINAGE OUT OF THE PLANTING BEDS.

PLANT SPACING


HETZL COLUMN JUNIPER 42" O.C.
MINT JULEP JUNIPER 42" O.C.
MAIDEN GRASS 36" O.C.
BROADMOOR JUNIPER 30" O.C.
ANTHONY WATERER SPIRAEA 21" O.C.
DWARF FOUNTAIN GRASS 'HAMELN' 18" O.C.
CRIMSON PYGMY BARBERRY 15" O.C.

NO.	DATE	DESCRIPTION	REVISIONS
1	2/14/12	ISSUED FOR REVIEW	




ALBERTSONS
AMIDON & 21ST STREET NORTH
WICHITA, KANSAS

ALBERTSONS
250 PARK CENTER BLVD., BOX 20
BOISE, IDAHO 83726

LANDSCAPE PLAN



JOB NUMBER	27000033	DESIGNED BY	STORE NUMBER
DRAWN BY	AR	APPROVED BY	
DATE	2/14/12	DATE	
SHEET NUMBER	LS102	OF	2




PLANTING REQUIREMENTS:
 STREET FRONTAGE TOTAL: 329 FT.
 GREATEST STREET WALL PERPENDICULAR: 72 FT.
 STREETYARD CALCULATIONS: 329-72 = 256ft = 2056 SQ. FT.
 REQUIRED TREES: 5
 PROPOSED TREES: 6.5

LEGAL DESCRIPTION:
 LOT 2, AMIDON PLAZA ADDITION
 WICHITA, SEDGWICK CO., KANSAS
ZONING:
 L.C. - LIMITED COMMERCIAL

LANDSCAPE PLAN
 APPROVED 7/30/10 BY NLS

PLANT MATERIALS LIST					
KEY	QUANTITY	COMMON NAME	BOTANICAL NAME	SIZE	CONDITION
SHRUBS / PERENNIALS					
CR	8	Carpet Rose	Rosa x 'nostrorum'	2 Gal.	Container
CBB	14	Compact Burning Bush	Euonymus alatus 'compacta'	2 Gal.	Container
FRG	17	Feather Reed Grass	Calamagrostis x acutiflora 'Karl Foester'	2 Gal.	Container
GP	51	Gnome Pyracantha	Pyracantha angustifolia 'Gnome'	2 Gal.	Container
SEJ	45	Sea Green Juniper	Juniperus chinensis 'Sea Green'	2 Gal.	Container
LBE	3	Loebark Elm	Ulmus parvifolia	2" Cal.	B & B
AM	4	Amur Maple	Acer tataricum var. ginnata	2" Cal.	B & B
ERB	3	Eastern Redbud	Cercis canadensis	2" Cal.	B & B
LANDSCAPE MATERIALS					
SOD AREA = 3,807.7698 SF (KANSAS PREMIUM BLEND FESCUE SOD) (TO BE IRRIGATED WITH SPRAYS)					
PLANTING BEDS ARE TO BE IRRIGATED WITH DRIP IRRIGATION, DRIP TUBING WITH 12" EMITTER SPACING BY RAINBIRD OR EQUAL					
SHREDDED CYPRESS MULCH = 215,7651 CU.YDS. (3" DEPTH FOR 3' DIA TREE RINGS AND ALL PLANTING BEDS)					

- LANDSCAPE NOTES**
- CONTRACTOR SHALL PROVIDE A MINIMUM FORTY EIGHT (48) HOURS ADVANCE NOTICE (EXCLUDING WEEKENDS AND HOLIDAYS) PRIOR TO BEGINNING ANY EXCAVATION, TO KANSAS ONE-CALL SYSTEM AT 811 TO REQUEST THE LOCATION OF ALL PUBLIC UTILITIES WITHIN THE PROJECT AREA.
 - CONTRACTOR SHALL SATISFY HIMSELF OF SURFACE AND SUBSURFACE CONDITIONS PRIOR TO BIDDING.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR PRESERVING PROPERTY IRONS. THE CONTRACTOR WILL BE REQUIRED TO RE-ESTABLISH ANY PROPERTY IRONS WHICH ARE DAMAGED OR DESTROYED BY HIS CONSTRUCTION OPERATIONS. SUCH IRONS SHALL BE RE-ESTABLISHED BY A LICENSED LAND SURVEYOR IN ACCORDANCE WITH STATE LAWS.
 - THE CONTRACTOR WILL BE REQUIRED TO WORK AROUND IMPROVEMENTS CONSTRUCTED UNDER OTHER PROJECTS AND SHALL BE RESPONSIBLE FOR REPAIR OF DAMAGE TO IMPROVEMENTS IN PLACE. COSTS FOR COORDINATION AND REPAIRS TO IMPROVEMENTS IN PLACE, IF REQUIRED, SHALL BE BORNE BY THE CONTRACTOR.
 - ALL PLANT MATERIAL SHALL BE HIGH-QUALITY NURSERY GROWN STOCK WHICH MEETS THE "AMERICAN ASSOCIATION OF NURSERYMEN" STANDARDS AS SPECIFIED BY THE "AMERICAN NATIONAL STANDARDS INSTITUTE" IN ANSI Z60.1-1986 OR AS MAY BE AMENDED IN THE FUTURE.
 - MULCH ALL SHRUB BEDS WITH A MINIMUM OF 3" SHREDDED CYPRESS MULCH.
 - ALL TURF AREAS TO BE SODDED WITH KANSAS PREMIUM BLEND FESCUE SOD.
 - ALL TURF AREAS TO HAVE A MINIMUM OF 6" TOPSOIL, FREE FROM ROCKS & DEBRIS.



THIS DRAWING IS AND SHALL REMAIN THE PROPERTY OF THE KROGER COMPANY. REPRODUCTION OR ALTERATION OF THIS DRAWING WITHOUT THE EXPRESS WRITTEN PERMISSION OF THE KROGER COMPANY IS PROHIBITED. (NOT PUBLISHED; ALL RIGHTS RESERVED)

NOTE TO CONTRACTOR:
 THIS SET OF DRAWINGS AND DOCUMENTS IS INTENDED AS A SET OF GUIDELINES FOR THE PROJECT AND ARE INTENDED TO BE USED IN CONJUNCTION WITH A SET OF CONSTRUCTION SPECIFICATIONS TO BE SUPPLIED BY OWNER. THEY MUST BE READ TO INCORPORATE ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES INCLUDING FEDERAL A.D.A. REQUIREMENTS. THIS SET ASSUMES THAT THERE ARE NO UNUSUAL SOIL CONDITIONS OR WIND LOADS. THE FAILURE OF THIS CONDITION MAY REQUIRE SIGNIFICANT CHANGES TO THESE DOCUMENTS. IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO CONFORM TO ALL APPLICABLE CODES AND TO INFORM THE OWNERS/ARCHITECTS OF ANY QUESTIONS OR CLARIFICATIONS WHICH ARE DESIRED. CONTRACTORS SHALL ALSO VISIT THE SITE BEFORE BIDDING. CONTRACTORS ARE REQUIRED TO KNOW ALL OBSERVABLE CONDITIONS AND APPLICABLE CODES.



No.	DESCRIPTION	DATE	REVISIONS	
			DES.	CHK.

Project #: 35-06742-089A-0645
 Designed By: RMH
 Drawn By: CAE
 Checked By: DKK
 Date: JULY 12, 2013
 Scale: 1:10
 Disk File:
 Model:

Address: 1950 W. 21ST. STREET
 DILLONS #89 WICHITA, KS