

44TH STREET SOUTH

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+00	41.56	10.05	85.18	12.39	85.18
0+50	50.43	3.33	93.94	6.24	179.12	18.62
1+00	51.03	3.41	47.36	2.90	226.48	21.52
1+25	51.28	2.86	27.60	1.84	254.08	23.36
1+40	48.08	3.77	17.47	1.28	271.56	24.64
1+50	46.26	4.72	135.32	9.44	406.88	34.08
2+24.79	51.44	2.72	52.95	1.29	459.83	35.37
2+50	61.97	0.05	142.26	0.05	602.08	35.42
3+02.86	83.35	0.00	131.24	0.00	733.32	35.42
3+50	66.98	0.00	65.99	0.26	799.31	35.68
3+78.50	58.05	0.49	47.37	0.24	846.68	35.92
4+00	60.94	0.12	108.20	0.09	954.88	36.01
4+42.84	75.45	0.00	20.44	0.00	975.32	36.01
4+50	78.71	0.00	167.39	0.00	1142.71	36.01
5+00	102.06	0.00	66.17	0.00	1208.88	36.01
5+16.84	110.13	0.00	84.42	0.00	1293.30	36.01
5+37.07	115.20	0.00	54.71	0.00	1348.01	36.01
5+50	113.28	0.00	68.58	0.00	1416.58	36.01
5+66.79	107.29	0.00	123.77	0.00	1540.36	36.01
6+00	93.97	0.00	155.95	0.00	1696.31	36.01
6+50	74.46	0.00	73.97	1.80	1770.28	37.82
6+78.99	63.35	3.02	49.30	8.82	1819.58	46.64
7+00	63.36	19.66	111.05	25.32	1930.63	71.96
7+50	56.58	7.68	90.10	13.91	2020.73	85.87
8+00	40.73	7.35	105.29	6.80	2126.02	92.68
8+50	72.99	0.00	120.62	0.59	2246.64	93.27
9+00	57.28	0.64	95.79	6.57	2342.43	99.84
9+50	46.17	6.46	76.50	19.09	2418.92	118.93
10+00	36.44	14.16	58.48	33.81	2477.40	152.75
10+50	26.72	22.36	40.47	49.46	2517.88	202.20
11+00	16.99	31.05	40.48	49.45	2558.36	251.65
11+50	26.73	22.35	58.52	33.78	2616.88	285.43
12+00	36.47	14.14	22.70	7.68	2639.58	293.11
12+16.11	39.61	11.60	54.41	10.89	2694.00	304.00
12+50	47.09	5.76	99.71	5.47	2793.71	309.47
13+00	60.60	0.15	65.33	0.08	2859.04	309.55
13+27.43	68.20	0.00	82.94	0.00	2941.98	309.55
13+57.68	79.85	0.00	0.00	0.00	2941.98	309.55

ST. PAUL


STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+38	65.75	0.00	28.34	0.00	28.34
0+50	61.79	0.00	100.65	1.43	128.99	1.43
1+00	46.91	1.54	63.87	5.73	192.86	7.15
1+40.25	38.78	6.14	13.65	2.36	206.50	9.52
1+50	36.80	7.02	59.08	16.38	265.58	25.90
2+00	27.00	10.68	13.14	5.54	278.72	31.44
2+13.35	26.14	11.67	39.13	14.70	317.85	46.13
2+50	31.51	10.12	67.85	13.50	385.70	59.64
3+00	41.77	4.56	27.99	2.57	413.69	62.21
3+17.73	43.49	3.27	39.00	4.05	452.69	66.26
3+42.77	40.63	5.47	0.00	0.00	452.69	66.26

CHASE

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+39.69	31.95	9.89	12.73	3.39	12.73
0+50	34.74	7.86	63.91	13.51	76.64	16.90
1+00	34.28	6.72	62.06	17.64	138.70	34.54
1+50	32.75	12.33	60.74	19.15	199.44	53.69
2+00	32.85	8.35	67.74	10.59	267.18	64.27
2+50	40.31	3.08	68.99	9.15	336.17	73.42
3+00	34.20	6.80	56.14	19.78	392.31	93.19
3+50	26.43	14.56	41.76	34.61	434.06	127.81
4+00	18.66	22.82	59.43	23.29	493.49	151.10
4+52.68	42.25	1.05	0.00	0.00	493.49	151.10

ST. PAUL CT.

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+35.03	23.29	17.88	9.78	6.28	9.78
0+45.59	26.75	14.26	33.53	11.94	43.32	18.23
0+70.58	45.71	11.55	41.49	12.05	84.81	30.28
0+95.58	43.91	14.48	39.01	15.36	123.82	45.65
1+20.33	41.21	19.04	10.07	7.61	133.88	53.25
1+30.58	11.82	21.04	3.47	6.96	137.35	60.21
1+45.57	0.68	4.04	0.00	0.00	137.35	60.21

Legacy 3rd Addition EARTHWORK CALCULATIONS WICHITA, KANSAS			
 Ruggles & Bohm, P.A. Engineering, Surveying, Land Planning	924 North Main Wichita, Kansas 67203 www.rbkansas.com		(316) 264-8008 (316) 264-4621 fax E-mail: info@rbkansas.com
	DRAWING FILE Details [Earthwork Calcs]	PROJECT NUMBER 472-84525	DESIGN E.J.G. DRAWN R.L.S. REVIEW UTILITY DATE Dec. 12, 2006