





ROSEBERRY COURT PARKING COURT

SERVING LOTS 21 THROUGH 36, BLOCK J, PLANEVIEW
SUBDIVISION NO. 1



IMPROVEMENT DISTRICT MAP




VICINITY MAP



PROJECT NO. 472-76-245-81360-000-000-001
818-76-245-50209-000-000-001
CITY OF WICHITA M. E. LINDEBAK CITY ENGINEER
LANDCO ENGINEERING CONSULTANT ENGINEER

B.M. El. 107.01 S-rim MH at Sta. 1+29, 18' R.
 B.M. El. 105.99 TC E-end Return SE-corner Intersection
 Roseberry St. & Roseberry Court


Scale 1" = 10'



NOTE:
 3" Asphalt Curb Constructed with this Project shall not be paid for directly, but shall be considered incidental to the cost of the 5" of 5" Asphalt Pavement placed.

EARTHWORK:


EXCAVATION	316.5 C.Y.	COMPACTED FILL (75%)	227.9 C.Y.
+10%	31.7 C.Y.	+10%	23.0 C.Y.
TOTAL	348.2 C.Y.	TOTAL	250.9 C.Y.



ROSEBERRY COURT PARKING COURT
 Serving Lots 21 through 36 inclusive, Block J, Planview Sub. No. 1
 Project No. 472-76-245-81360-000-000-001
 813-76-245-56209-000-000-001
CITY OF WICHITA **M. E. LINDEBAK** **CITY ENGINEER**
LANDCO ENGINEERING **CONSULTANT ENGINEER**
 BOOK 3TT DRAWN BY RH DATE 6/84

5" ASPHALTIC CONCRETE PAVEMENT w.
3" BITUMINOUS BASE
TYPICAL TRANSVERSE SECTION


Scale 1" = 5'



NOTE:



- 1) A tack coat of emulsified asphalt (SC-1H or CSS-1H) shall be applied at an approximate rate of 0.05 gallons per square yard between each lift of asphaltic material.
- 2) Construction Joints in each lift shall be staggered a minimum of one (1) foot from joints in preceding lifts.

BUMPER BLOCK & PARKING STALL
DETAIL




NOTE:


- 1) The Contractor Shall Install 38 Precast Concrete Bumper Blocks as Shown. The Bumper Blocks Shall be six-foot in Length, Seven to Eight inches Wide at the Base, Approximately Three Inches Wide at the Top, and Five to Six inches in Overall Height, with a Slope from about Center Height to the Top. Concrete used in Manufacture Shall be Designed for a Compressive Strength to Exceed 3000 psi, and Units to be Reinforced full Length with One or More Steel Reinforcing Rods. The Finish Shall be Smooth, and Off-White in Color. Each Bumper Block Shall have a Hole for Steel Anchor Pins Located near each End, of 48" or 3/4" Diameter.
- 2) Stall Lines shall be painted 6" in width. Paint used shall meet City of Wichita Traffic Operations and Maintenance Division Specification for Heated Rapid Dry Pavement Marking Paint.



DETAIL: 5" ASPHALT CURB
OTHER SUITABLE CURB SECTION
MAY BE USED WITH PERMISSION
OF FIELD ENGINEER



ROSEBERRY COURT PARKING COURT
472-76-245-81360-000-000-001
818-76-245-50209-000-000-001



ROSEBEARY COURT
SEAVING Lots 21-36, inclusive, Blk 3
Platview Sub. No. 1
472-76-245-81340-000-000-001
810-7-245-50209-000-000-001

TOTAL E.V.C.
316.5 C.Y.