

Thoroughbred

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+37	128.10	0.00	256.44	0.00	256.44
1+00	91.71	0.00	139.61	0.00	396.06	0.00
1+50	59.07	0.00	87.22	9.02	483.28	9.02
2+00	35.13	9.75	47.93	32.56	531.21	41.58
2+50	16.64	25.42	16.87	67.83	548.08	109.41
3+00	1.59	47.84	1.47	127.52	549.55	236.93
3+50	0.00	89.88	0.00	206.41	549.55	443.35
4+00	0.00	133.04	0.00	238.15	549.55	681.49
4+50	0.00	124.16	0.00	215.33	549.55	896.82
5+00	0.00	108.40	0.00	191.83	549.55	1088.65
5+50	0.00	98.78	0.00	173.94	549.55	1262.60
6+00	0.00	89.08	0.00	116.29	549.55	1378.88
6+36.58	0.00	82.59	0.00	26.39	549.55	1405.27
6+45.48	0.00	80.63	0.00	0.00	549.55	1405.27

Prince

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+00	75.18	0.00	106.57	3.19	106.57
0+50	39.91	3.44	76.73	10.11	183.30	13.30
1+03	38.27	6.86	0.00	0.00	183.30	13.30

Thoroughbred Court

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+37	0.00	67.86	0.00	33.25	0.00
0+50	0.00	70.25	0.00	139.15	0.00	172.40
1+00	0.00	80.03	0.00	51.33	0.00	223.73
1+16.80	0.00	84.96	0.00	98.69	0.00	322.42
1+41.44	0.00	131.32	0.00	144.22	0.00	466.64
1+66.79	0.00	175.90	0.00	139.89	0.00	606.53
1+91.89	0.00	125.05	0.00	37.39	0.00	643.92
2+01.79	0.00	78.91	0.00	51.48	0.00	695.40
2+16.77	0.00	106.67	0.00	0.00	0.00	695.40

Kent. Ln 1

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+15.27	6.01	37.50	21.34	51.36	21.34
0+60	19.76	24.51	14.63	88.40	35.98	139.77
1+00	0.00	94.83	2.37	132.29	38.35	272.06
1+50	2.56	48.04	25.62	64.07	63.97	336.13
2+00	25.11	21.15	24.40	18.75	88.38	354.87
2+25	27.60	19.34	22.77	19.50	111.15	374.38
2+50	21.59	22.79	21.10	68.35	132.25	442.73
3+00	2.79	45.42	19.88	66.81	152.13	509.53
3+50.64	19.72	23.14	38.30	38.44	190.43	547.97
4+00	21.96	20.11	47.25	35.33	237.68	583.30
4+53.06	25.83	17.36	50.59	25.55	288.27	608.85
5+00	32.37	12.02	66.00	17.47	354.27	626.31
5+50	38.91	6.84	72.27	12.44	426.54	638.75
6+00	39.15	6.59	68.43	15.41	494.97	654.16
6+50	34.76	10.05	48.91	9.20	543.88	663.35
6+84.20	42.46	4.47	25.73	2.25	569.61	665.60
7+00	45.48	3.20	102.66	3.01	672.27	668.60
7+50	65.39	0.04	127.84	0.05	800.11	668.66
8+00	72.67	0.01	116.45	0.01	916.56	668.67
8+42.92	73.84	0.00	156.29	0.00	1072.84	668.68
9+00	71.13	0.00	123.72	0.10	1196.56	668.77
9+50	60.47	0.13	100.13	1.01	1296.69	669.78
10+00	46.95	1.19	76.72	3.67	1373.41	673.45
10+48.49	38.38	3.41	0.00	0.00	1373.41	673.45

Kent. Ln 2A

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+36.66	40.51	6.79	19.47	3.84	19.47
0+50	38.39	8.38	62.79	22.50	82.26	26.34
1+00	29.48	15.57	46.03	35.13	128.28	61.47
1+50	20.25	22.21	0.00	0.00	128.28	61.47

Kent. Ln 2

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+40.01	39.55	4.44	88.97	6.70	88.97
1+00	40.13	2.36	65.44	1.48	154.41	8.18
1+36.53	56.01	0.13	162.20	0.15	316.61	8.33
2+00	81.99	0.00	138.88	0.00	455.50	8.33
2+50	68.00	0.00	112.19	0.00	567.68	8.33
3+00	53.16	0.00	87.03	1.04	654.71	9.37
3+50	40.83	1.12	73.25	4.51	727.96	13.88
4+00	38.28	3.74	66.34	9.59	794.30	23.47
4+49.40	34.24	6.74	61.78	15.85	856.08	39.32
5+00	31.88	8.89	58.73	16.84	914.81	56.15
5+49.70	32.05	8.65	57.14	18.88	971.95	75.04
6+00	29.33	11.33	49.98	32.81	1021.93	107.85
6+54.96	19.78	20.91	27.12	41.07	1049.05	148.91
7+00	12.74	28.33	16.58	60.64	1065.63	209.55
7+50	5.17	37.16	5.09	83.10	1070.72	292.66
8+00	0.33	52.59	0.31	127.54	1071.03	420.20
8+50	0.00	85.16	0.00	188.83	1071.03	609.03
9+00	0.00	118.77	0.00	158.02	1071.03	767.05
9+32.79	0.00	141.45	0.00	0.00	1071.03	767.05

8-28-07

Cheryl's Hollow 2nd Addition
EARTHWORK CALCULATIONS
WICHITA, KANSAS



Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning

924 North Main
Wichita, Kansas 67203
www.rbkansas.com

DESIGN: KWL
DRAWN: RLS
REVIEW: [blank]
UTILITY: [blank]

PROJECT NUMBER: 472-84544
DATE: Aug. 7, 2007

SHEET 43 OF 45