B.M. 127.39 "S" in Globe, W. Curb Kessler. S.L. 16th.
B.M. 127.74 N.E. Cor. Conc. Step, House 1691 N. Kessler.

B.M. 130.95 "H" in Richie, Top W. Curb Kessler. 1' N. of N.L. 17th.

Scale 1"=20'

Baseline = E. 16th Kessler.

P.I. 128.61 200' V.C.

P.I. 133.50 200' V.C.

+0.42% +0.4 Walk

Graduate Walk 0.4 to 0.7

+2.45%

+0.7 Walk

-1.14%

Graduate Walk 0.7 to 0.4

Existing 4' Walk

Proposed 4' Walk

ST.

No Crown

Conc. G.

Proposed 4' Walk

Existing Conc.

Match Existing

30'

Full Crown

16 Crown

KESSLER

AVE.

Proposed 4' Walk

No Crown

16TH

+0.42% +0.4 Walk

P.I. 128.60 200' V.C.

Graduate Walk 0.4 to 0.7

+2.70%

+0.7 Walk

P.I. 134.00 200' V.C.

-1.14% +0.4 Walk

+0.7 Walk

-1.46%

Graduate Walk 0.7 to 0.4

Proposed 4' Walk

KESSLER

Full Crown

No Crown

30' Match Existing

Existing 17' C. Pavement

Remove Existing Curb & Gutter

17TH

-1.46% +0.4 Walk

NOTE:
Contractor to Grade and Clear Parking for Proposed Sidewalk. Compact Fill in Sidewalk Area: Sidewalk to be Constructed by "OTHERS.

EARTHWORK QUANTITIES

Property	Excavation	Comp. Fill	C.Y. Excavation	Comp. Fill
	1878.0 C.Y.	4.3 C.Y.	209.1 C.Y.	1.1 C.Y.
+10%	187.8 "	0.4 "	23.9 "	0.1 "
	2065.8 C.Y.	4.7 C.Y.	233.0 C.Y.	1.2 C.Y.

B. E. SMITH LICENSED 436 KANSAS PROFESSIONAL ENGINEER

1/2

KESSLER AVE.

From S.L. 16th Street
To S.L. 17th Street
26'-2'-30' A.C. & Curb
B.E. SMITH CITY ENGINEER
CITY OF WICHITA, KANSAS
DATE SEPT. 1963 C 17-95