



CONTRACTOR TO REMOVE AND DISPOSE OF DRIVE ENTRANCE CULVERTS AND FILL DITCHES TO R/W LINE TO PROVIDE POSITIVE DRAINAGE TO CURB.

CONSTRUCT 5" A.C. PAVEMENT HOOKUP WITH 5" CRUSHED ROCK BASE

CONSTRUCT VALLEY GUTTER PAVEMENT. 7" REINFORCED CONCRETE W/ 5" CRUSHED ROCK BASE AND MONOLITHIC EDGE CURB (6 5/8")

CONSTRUCT COMBINED FULL HEIGHT CURB AND GUTTER (6 5/8" & 1 1/2") BOTH SIDES

CONSTRUCT 6" CONCRETE DRIVE PAVEMENT

REMOVE AND RESET EXISTING SIGN

ADJUST WATER VALVE TOP FROM 1329.85 TO 1329.46

CONSTRUCT 5" ASPHALT CONCRETE PAVEMENT W/ 5" CRUSHED ROCK BASE

CONSTRUCT TYPE 1A INLET HOOKUP (BOTH SIDES)

CONSTRUCT VALLEY GUTTER PAVEMENT. 7" REINFORCED CONCRETE W/ 5" CRUSHED ROCK BASE AND MONOLITHIC EDGE CURB (6 5/8")

SAW CUT EXISTING PAVEMENT TO A NEAT LINE AND MATCH.

DEWATERING WELLS TO BE ABANDONED IN ACCORDANCE WITH H.D.H.E. SPECIFICATIONS.

- A.C. MAT PAVEMENT TO BE REMOVED
- TREE ROW TO BE REMOVED
- TREE TO BE REMOVED
- PIPE TO BE REMOVED

<b>PAVING IMPROVEMENTS</b>				
<b>51st Street North</b>				
<b>WICHITA, KANSAS</b>				
	Ruggles & Bohm, P.A. Engineering, Surveying, Land Planning			
	924 North Main Wichita, Kansas 67203 www.rbkansas.com	(316) 264-8008 (316) 264-4621 fax E-mail: info@rbkansas.com	DESIGN: KWL DRAWN: RA REVIEW: RA UTILITY: RA	SHEET: 6 OF 31
DRAWING FILE Paving {51st - 3}	PROJECT NUMBER 472-84550 472-84551	DATE Oct. 31, 2007	SHEET 6 OF 31	SHEET 6 OF 31