B.M. 153.008 S.W. Cor. Conc. Porch NE. Pinecrest & Lincoln No. "858
B.M. 157.30 G in Globe S. Curb Morris, E.L. Pinecrest
B.M. 156.67 G in Globe N. Curb Morris, W.L. Sylvan Lane
B.M. 161.51 G in Globe W. Curb Beverley Dr, N.L. Morris

PINECREST AVENUE

SYLVAN LANE

BEVERLEY DRIVE

MORRIS STREET

1.15 E. Of C.L.

1.70 Ave. Wk. 10.5% on 02

-0.29% Wk. 08' from 0+00 to 1+00 Grade to 0.4 @ 2+70

-0.37% Wk. 0.4'

NO GRADE SET

Meet Existing Pavement

Cb. & Gtr. Only

Concrete

V.C.

A.C. Pavt.

Flat Concrete Intersection

Drains South

Sta. 0+00 Bk. Curb Line Elev. 0.5 Under Walk

7.5% Cr. Off

1"=20'

MORRIS ST.
W.L. PINECREST AVE. TO W.L. BEVERLEY DR.
26' A.C. CONSTRUCT COMBINED
CB. & GTR. WHERE NECESSARY
CITY OF WICHITA, KAN.

B.E. SMITH
CITY ENGINEER
JAN. 1953
PROJ. NO. C-12-167