Surv. [illegible]
Dr.
Checked

N

B.M. = 112.80 ± Cut on sidewalk, NE. cor. 1st. National Bank Building

Elev. = 1.0

Note - all available dirt & sand to remain on this project.

NOTICE TO CONTRACTOR

This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will reimburse the City of Wichita for all cost of Engineering, Plans, and Inspection.

End of Project

match finish floor grade

adjust 2x2' grate top of grate El. 112.05

adjust 2x2' grate top of grate El. 112.05

remove 5½ existing island curb

remove 4' planter (salvage earth for sandfill at k. plug leads E.S.

match existing curb return at N.E. Main St.

match finish floor grade

Note: Sew pipe to match floor grade w. existing floor elev. New BUILDING CONSTRUCTION

3' conc. walk to remain in place.

under-ground tanks (1'x 22' round.)

3' conc. walk to remain in place.

vent

vent

FIRST NATIONAL BANK BLDG

MAIN STREET

+0.20½ (6 Fla. grade)

Note - Set N.E. grades as shown on N.S. grade of walk.

"ALLEY Cross-section"

STEEL PATTERN - S½ ALLEY

STEEL PATTERN - N½ ALLEY

"Bill Of Materials"		
Quan.	Unit	Item
900	S.Y.	8" Concrete Pavement
2120	Lbs.	Reinforcing Steel
180	L.F.	Key Joint
625	S.F.	Expansion Rem.
135	S.F.	Dowel Cap Rem.
125	L.F.	Curb Rem.
6	Ea.	2'x 2' grate Rem.
2	Ea.	2'x 2' grate adjusted
5	Ea.	Manhole "
1	Ea.	Observation hole "
2	Ea.	Pipe plugs
10	L.F.	Saw Joint

"ALLEY NO. of DOUGLAS"

Betw. Alley east of Water Street to N.L. Main Street.

- 20 ft. - 8" Reinforced Concrete -

CITY OF WICHITA, KANSAS

B.E. Smith ... City Engineer

Date: Private Contract

B.E. SMITH LICENSED KANSAS 436 PROFESSIONAL ENGINEER