

R.M. 142.9 RR. Spike, N.S. RR. S.W. Ridge Road & 11TH STREET



ROAD

RIDGE

AVENUE

SUMMITLAWN

11TH

STREET.

Repair Asphalt mat as required.

Base Pav'l Area is to be Re-constructed with 5" 3" Jack Rock Mix Concrete Over layed with 2" Asphalt.

LIST OF QUANTITIES.	
174 sq yds	5" & 3" Jack A.C. Pavement
77 sq yds	7" Concrete pavement
50 lin ft	Integral curb
60 lin ft	Comb. Curb & Gutter
1,440 lbs	Rein. Steel
150 lin ft	Key Joint
See Note	Pavement Removed

* NOTE: TO CONTRACTOR. Existing Intersection is A.C. Mat and Concrete. Contractor will be responsible for estimating removal quantities.

NOTE TO CONTRACTOR:
This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will reimburse the City of Wichita for all cost of Engineering, Plans, and Inspection.

11TH ST and SUMMITLAWN AVE
RECONSTRUCTION of INTERSECTION.
Asphaltic Concrete & Curb.
CITY of WICHITA, KANSAS
B.E. SMITH CITY ENGINEER
DATE: PRIVATE PROJECT.