B.M. 103.79 N.E. Cor. Conc. Walk 30' (Rt) Sta. 0+54

B.M. 102.88 "P" in P.K.S. top E. Curb Bonn, S.L. Dora

B.M. 102.64 "G" in Globe top West Curb Hiram, N.L. May

B.M. 103.83 "G" in Globe top North Curb Dora, W. end Radius, W.L. Hiram

Remove pipe & grade approach. Ditch to drain onto pavement.

N

Scale: 1" = 20'

U.F.G. #31 U.F.G.

EVERETT AVENUE

HIRAM AVENUE

DORA AVENUE

BONN AVENUE

0+00 0+50 1+00 1+34.5 1+59.5 2+00 2+50 2+87.0 2+94(P) 3+24 3+54 3+61.0 4+00 4+50 4+80.25 +85.75(P) +03.75 5+09.25 5+50 6+00 6+39.28(M)

-0.157% .2 to .6 Wk.

+0.377% .7 Wk.

-0.174% .2 to .7 Wk.

+0.356% .6 to .7 Wk.

14' ALLEY

16' ALLEY

Sta. 1+34.5 (P) 29.98 (M) Iron 30.03 (Rd)

Sta. 2+94.0 (M) Iron 30.03 (Rd)

Sta. 3+24 (M) Angle Iron on E.

Sta. 1+59.5 (P) Iron 30.0 (Rd) 16' Alley

Sta. 4+80.25 (M) Iron 31.02 (Rd)

Sta. 5+09.25 (P) Iron 31.02 (Rd)

Sta. 0+00 (M) Iron 30.0 (Rd)

Sta. 6+38.95 (M) Iron 30.0 (Rd)

Down 6" Pipe 2.3 (Rd)

6" Pipe 1.9 (Rd)

Center of 5'-5" Elm Trees & Common Stump

4' Ch. Link Fence

10' Conc. Slab Porch

Metal Wire Fence

8" Conc. Curb

Brick Bldg. (Church)

12"x18" M. Pipe

18"x18" C.M.P.

15"x15" C.M.P.

8" Conc. Curb & Gutter

Conc. Int.

Conc. Walk

Match Conc.

Match Curb

Bk. Curb 3.10 (E)

Bk. Curb 3.08 (E)

Bk. Curb 3.15 (E)

Bk. Curb 3.13 (E)

Bk. Curb 3.13 (W)

Bk. Curb 3.15 (W)

Bk. Curb 3.08 (W)

Bk. Curb 3.10 (W)

2.95 Cb. 2.92 Cb. 3.24 Cb. 3.37 Cb.

PROPERTY

	EXC.	COMP. FILL
	579 Cu. Yds.	85 Cu. Yds.
+10%	58 " "	8 " "
Totals	637 Cu. Yds.	93 Cu. Yds.

CITY

EXC.	COMP. FILL
216 Cu. Yds.	8 Cu. Yds.
22 " "	1 " "
238 Cu. Yds.	9 Cu. Yds.

JOHN E. SALLEE 621 REGISTERED PROFESSIONAL ENGINEER STATE OF KANSAS

B.E. SMITH 435 REGISTERED PROFESSIONAL ENGINEER STATE OF KANSAS

DORA AVENUE

FROM E.L. EVERETT AVE. TO W.L. HIRAM AVENUE

30'-6" Conc. & Int. Curb

B.E. SMITH CITY ENGINEER
CITY OF WICHITA, KANSAS

JULY 1963 Project No. C13-39