



ELIZABETH AVENUE


S.L. LOT 7, BLOCK E, TO N.L. LOT 4, BLOCK E,
VILM GARDENS SECOND ADDITION
472 76 245 80396 000 000 001



COMBINED CURB & GUTTER



COMBINED CURB & GUTTER




TYPICAL SECTION

3" ASPHALTIC CONCRETE PAVEMENT WITH BITUMINOUS BASE

A TACK COAT OF EMULSIFIED ASPHALT (SS-1H) SHALL BE APPLIED AT AN APPROXIMATE RATE OF 0.05 GALLONS PER SQ. YD. BETWEEN LIFTS OF ASPHALTIC MATERIALS WHEN ORDERED BY THE ENGINEER. TACK COAT WILL NOT BE PAID FOR DIRECTLY AND SHALL BE CONSIDERED AS SUBSIDIARY TO PRICE BID FOR ASPHALTIC PAVEMENT. BITUMINOUS BASE AND ASPHALTIC CONCRETE WEARING SURFACE SHALL BE PLACED WITH A LAYDOWN MACHINE HAVING AUTOMATIC CONTROLS FOR CROWN AND GRADE. CONSTRUCTION JOINTS IN EACH LIFT SHALL BE STAGGERED A MINIMUM DISTANCE OF 1' WITH JOINTS IN PRECEDING LIFTS AND SUCH THAT A JOINT WILL BE CONSTRUCTED ON THE PAVEMENT CENTERLINE IN THE TOP LIFT.

DETAIL OF TRANSVERSE CONSTRUCTION JOINTS



TRANSVERSE CONSTRUCTION JOINTS SHALL BE CONSTRUCTED IN FLEXIBLE BASE PAVEMENTS AT LOCATIONS WHERE PAVEMENT TEMPORARILY ENDS TO FACILITATE FUTURE PAVEMENT CONSTRUCTION AS SHOWN BY DETAIL. THE COST OF CONSTRUCTING THE TRANSVERSE CONSTRUCTION JOINTS SHALL NOT BE MEASURED OR PAID FOR DIRECTLY BUT SHALL BE INCLUDED IN THE BID PRICE FOR SQUARE YARDS OF ASPHALTIC CONCRETE PAVEMENT.

The A.C. pavement between the Comb. Curb & Gutter shall be paid as 3" A.C. Pavement (6 Bituminous Base). The Bituminous Base under the Comb. Curb & Gutter shall be paid as 3" Bituminous Base.



CITY OF WICHITA, KANSAS


DEPARTMENT OF PUBLIC WORKS — ENGINEERING

DEAN SELLERS Acting CITY ENGINEER

DATE _____ PROJ. NO. DAKS 576035 (1/2)


Scale: 1" = 20'

No More Than 1-20' Drive Or The Equivalent To Be Constructed.



 ~ Indicates
Fence Removal.

<u>Earthwork</u>		<u>Quantities</u>	
<u>Property</u>		<u>City</u>	
Excavation =	2024.6 cy	Excavation =	130.8 cy
+ 10 % =	202.5 -	+ 10 % =	13.1 -
Total =	2227.1 -	Total =	143.9 -
<u>Manipulation = 1919.5 cy</u>		<u>Manipulation = 175.6 cy</u>	

ELIZABETH AVENUE
S.L. Lot 7, Block E, to N.L. Lot 4, Block E,
Viim Gardens Second Addition
(26-2-30 Asphaltic Concrete Pav't.)

CITY OF WICHITA, KANSAS
472 76 245 80396 000 000 001
DEAN SELLERS **CITY ENGINEER**

PROJECT NUMBER: DAKS 576⁷/₂
DATE: