


HIGHLAND CEMETERY FENCING

CITY OF WICHITA, KANSAS

GENERAL NOTES

PROJECT INCLUDES THE RELOCATION OF FOUR STONE ENTRY WAY COLUMNS AND THE CONSTRUCTION OF THREE NEW STONE CORNER AND END FENCE COLUMNS. THE CONTRACTOR SHALL DISMANTLE THE FOUR ENTRY WAY COLUMNS AND REASSEMBLE THEM IN THE NEW LOCATION. CONTRACTOR WILL BE REQUIRED TO REPLACE ANY MATERIAL WHICH IS DAMAGED IN THE DISMANTLING OF THE EXISTING COLUMNS WITH NEW MATERIAL EQUAL IN APPEARANCE AND QUALITY TO THE ORIGINAL MATERIALS. THE THREE NEW STONE CORNER AND END POSTS SHALL BE DUPLICATES OF THE ORIGINAL ENTRY WAY COLUMNS IN APPEARANCE AND QUALITY EXCEPT AN ENGRAVED STONE CEMETERY NAME MARKER WILL NOT BE REQUIRED IN THE THREE NEW COLUMNS.

INDEX NO. 131250





LOCATION MAP


***** = CONSTRUCTION LOCATION



M. E. LINDEBAK, P.E., CITY ENGINEER

PROJECT DESCRIPTION		
PROJECT NUMBER		
BOOK NO.	APPROVED BY	DATE
DRAWN BY		REVISED
CITY OF WICHITA		









November 27, 1990
Wichita, Kansas
W/A (131250) (724000)
CC Approval 08-14-90: Resol. --
Does not affect existing traffic

To the City Council
Wichita, Kansas

Dear Councilmembers:

PRELIMINARY ESTIMATE of the cost of constructing Highland Cemetery Fencing.

All work done and all materials furnished to be in accordance with plans and specifications on file in the office of the City Engineer.

Limestone Columns Dismantled and Re-constructed	4 each @ 2,000.00	8,000.00
Limestone Columns Constructed (new construction)	3 each @ 2,000.00	6,000.00
Furnish and Install 6 ft. black wrought iron fence (Galvanized Commercial rail and picket)	2,300 l.f. @ 30.00	69,000.00
5' High Chain Link Fence Removed	1,050 l.f. @ 5.00	5,250.00
Posts Removed	10 each @ 15.00	150.00
		<u>\$88,400.00</u>
Engineering and Inspection		11,492.00
Publication		200.00
Total Estimated Cost -		\$100,092.00

CITY OF WICHITA)
STATE OF KANSAS) SS

I do solemnly swear that the above amount is correct, reasonable and just.

Mike Lindebak, City Engineer

Sworn to and subscribed before me this ____ day of _____, 1990.

City Clerk

EXHIBIT _____

FIRST PUBLISHED IN THE DAILY REPORTER

SEALED PROPOSALS

Notice is hereby given that bids will be received at the office of the Purchasing Manager up to 10:00 a.m., Friday, December 7, 1990 for constructing Highland Cemetery Fencing.

Limestone Columns Dismantled and Re-constructed 4 each
Limestone Columns Constructed (new construction) 3 each
Furnish & Install 6 ft. black wrought iron fence (Galvanized Commercial rail & picket) 2,300 l.f.
5' High Chain Link Fence Removed 1,050 l.f.
Posts Removed 10 each

All bids received will thereafter be publicly opened, read aloud and considered by the Board of Bids and Contracts.

All work to be done under the direction and supervision of the City Manager and according to plans and specifications on file in the office of the City Engineer.

Bidders will be required to enclose a bid bond in the amount of five per cent (5%) with each as a guarantee of good faith.

The Wichita City Council reserves the right to reject any and all bids.

Dated at Wichita, Kansas, _____

Pat Burnett, Deputy City Clerk

/s/

1990 REVISED.
BUDGET
\$153,910.00

HIGHLAND CEMETERY FENCING.

INDEX No. 131250

Form 724000

PRELIMINARY ESTIMATE

4 Limestone Columns Dismantled and Re-constructed	@	2000.00	8000.00
3 Limestone Columns Constructed (NEW CONSTRUCTION)	@	2000.00	6000.00
2300 FURNISH AND INSTALL 6 FT. BLACK WROUGHT IRON FENCE (GALVANIZED COMMERCIAL RAIL AND PICKET)	@	30.00	69000.00
1050 L.F. 5' HIGH CHAIN LINK FENCE REMOVED	@	5.00	5250.00
10 POSTS REMOVED	EAH @	15.00	150.00

CONSTRUCTION SUB-TOTAL	88400.00
ENGINEERING (13%)	11492.00
PUBL	200.00
GRAND TOTAL	\$100,092.00

60 Working Days
Bid Dec. 7, 1990
Special Provisions Required
Insufficient Impact on Traffic

5410