...E. cor. NE. corner bottom conc. step
...ress # 1503 W Pawnee

Pawnee Ave.

190'

1.0'

1.0'

65'

Sta 1+21.5 Const.
2'x2' Drop Inlet

Sta 0+00
Existing Inlet

91'

Elizabeth Ave.

Sta 2+30 Const.
2'x2' Drop Inlet

...ale 1"=20'
...cale 1"=20' Horz
1"=5' Vert.

Sta 0+00
Existing Inlet

Sta 1+21.5 Const.
2'x2' Drop Inlet

Sta 2+30 Const.
2'x2' Drop Inlet

Existing Asphalt

Existing Ground

set top inlet elev @ 99.83

Proposed Asphalt Parking Lot

set top inlet elev @ 99.83

2-1" water lines

100

95

90

Sta 0+55
9" S.S. hookup
top 96.22

Sta 0+00 96.83 Flo 18 Out
96.48 Flo In

96.98

97.09 Flo

97.33

97.92

108.5 Lin. Ft of 15" C.M.P.
@ 0.3 % Grade

121.5± Lin. Ft. of 15" C.M.P.
@ 0.5 % Grade

0 1

Revised 3-1-77

2

PRIVATE STORM SEWER EXTENSION FOR
APPLEGATE'S LANDING AT PAWNEE & ELIZABETH

CITY OF WICHITA
R. W. LINN CITY ENGINEER
PROJECT NO. DBKW707006

NOTE: [illegible]
This sheet [illegible]

APPROVED AS NOTED
BY CITY ENGINEER OF WICHITA
Sanitary [illegible]
Storm Sewer [illegible]
Drainage [illegible]

Note: Replace the 4" Clay Pipe Sanitary Sewer hookup with 9" Ductile Iron Pipe a minimum distance of 2.5 ft. on both sides of the center line Storm Sewer. Concrete Collars must be installed on the joints between the Iron & Clay pipe.