Bm. 188.31 Step Bench & Side Fence Post Approx. 440' East of N.W. cor. Lot 8.

KAPAUN 2ND ADDITION

Sta 2407$ Const. Inlet & Std. Drop Inlets (2 Doubles & 1 Single) Top = 1864

Install 23 cy Type 3 Rip Rap

Wire & Fence

Wood Fence

30' Fire Lane & Drainage Easement

1 Drop Sta 1400

Sta 0488 Begin 36" RCP & End Section

Proposed CC & Apron

Proposed Building

UNPLATTED

8

KAPAUN IST ADDITION

Scale: 1"=20' Hor. 1"=5' Vert.

Site Location

KAPAUN FIRST ADDITION

CENTRAL AVE.

WOODLAWN

LOCATION MAP

Note-
Contractor to construct Std. Drop Inlets (2 Doubles and 1 Single) See detail.
Remove & Replace if necessary amount of wire fence.
Contractor to install End Section (Approximately 36" pipe length)

Existing Ground

Proposed Grade

Grade Swale to Existing Ditch Elev.

Install 23 cy Type 3 Rip Rap

Sta 0488 Begin 36" RCP & End Section

Sta 1400 Const. 5 Std. Drop Inlets (2 Doubles & 1 Single)

185

180

175

170

119$ L.F. 36" RCP @ 1.54 %

Existing Ditch

Station 0488 1400 1460 1600 1640$

CITY OF WICHITA

APPROVED: Approval does not relieve the contractor from any responsibility for errors or deviations from the contract requirements or for any deficiencies of equipment, work, or materials.

Date 11/30/82

Engineering Div. EJG

NOTE TO CONTRACTOR

This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will prepay the City of Wichita for all costs of inspection.

PLAN SURVEYED PLOTTED CHECKED RIGHT OF WAY CHECKED NOTE BOOK NO.

PROFILE SURVEYED PLOTTED CHECKED STRUCTURE DETAILS CHECKED NOTE BOOK NO.

BY DATE

PRIVATE STORM SEWER TO SERVE PART OF LOT 8, KAPAUN IST ADDITION

PROJ. NO. 468-76-245-80000.-000-000-008

CITY OF WICHITA, KS.

BAUGHMAN COMPANY, P.A.
SURVEYING & ENGINEERING
316/263-7271 • 330 LAURA • WICHITA, KANSAS 67211

RIGHT-WOOTEN 8470 LICENSED PROFESSIONAL ENGINEER

PLATE 1 - PLAN - PROFILE - F.A.S.
CLEARPRINT PAPER CO., S.F. CAL.
NO. 1000H-1

11 5 3 1/1