B.M. 116.66 S.E. Cor. Conc. Step 3 Side Ho. #201 N. Richmond

Sta on N. R.

Excavation

Prop.	City
265.8	0.4
+165 -65.4	+0 -0
279.2 (05)	2.4 (05)

0+00 Beg 5' Walk 1' Ext.
0+19 6" Tree 68' Ext.
0+48 6" Tree 67' Ext.
3.71 Lilac Hedge 33' Ft. to Bk. Of
1+06 3" Tree 28' Ext.
1+65 End 5' Walk 1.6' & Beg 6' Walk 2' Ext.
1+70 Manhole 17' Ext.
1+83 R.P. 18' Ext.
1+88 End 2.5' & Beg 5' Walk 1' Ext.
1+98 6" Tree 51' Ext.
2+43 36" Tree 6' Ext.
2+46 18" Tree 11' Ext.
2+88 18" Tree 1' Ext.
2+98 40" Tree 1' Ext.
3+05 12" Tree 1' Ext.
3+13 36" Tree 4.1' Ext.
3+16 Back Of Walk N & Beg Pvt.

-0.165%

0+00 0+50 1+00 1+50 2+00 2+50 3+00 3+50

Curve 1.5°
Rad. 3820.1'
Tan. 57.3'
Arc Length 114.6'
Area 0.4 Acre
Ave. Depth 0.9'
Excavation 1.3 Cu. Yd.

0-46' Thimble

Ave.

5' Conc. Walk

Meridian

Sedgwick

St.

Conc. Pvmt.

Mh.

Mh.

Heat. Exist. Pvmt.

Conc. Pvmt.

Note to Field Engineer & Contractor:
Remove & Replace Existing Curb & Gutter If Necessary To Align With New Curb.

1 St

30'

78.0'

-0.168% W/E 0.5'

Survey RJL Bk. W-7
Plan RJ
Ckd. AC
Checked JT

1 St St.
E.L. Meridian to W.L. Sedgwick
30' Conc. & Cb.
City of Wichita Kansas
B.E. Smith City Engineer
Oct. 1953 Proj. No. C-13-202

B.E. Smith Licensed 436 Kansas Engineer

1/1

12