Warren Bros. Co. Bituminous Plant 24 Ed. Chanute

1+00 Alley 1+50 2+00 7" Conc. Sawcut 7" Conc. 13th ST.

3+00 JACKSON AVE 3+50 7" Conc. 7" Conc. 13th ST.

5+00 Alley 5+50 6" Drive 7" Conc. 13th ST.

7+00 LEWELLEN AVE 7+50 8+00 6" Drive 7" Conc. Sawcut 7" Conc. 13th ST.

8+50 9+00 6" Drive 7" Conc. 13th ST.

NOTE:

FIELD ENGR. & CONTRACTOR

Cross hatching indicates area of removal & replacement.

Alleys & Drives replaced will be RAMP TYPE.

B.E. SMITH LICENSED KANSAS PROFESSIONAL ENGINEER 436

Reconstruction Of Drives & Alley Returns On 13th. St. Waco to Little Ark. River

City Of Wichita, Kansas
B.E. Smith City Engineer
Date Proj. 77-106

Survey 1/16 Blk 2 Addition Chicago

Steel 168 LF 3/4" Mastic 103.4 LF 57.0 LF

57.5 + 13.0 = 70.5 LF Saw Cut

NOTE:

FIELD ENGR. & CONTRACTOR

Cross hatching indicates area of removal & replacement.

Alleys & Drives replaced will be RAMP TYPE.

Reconstruction Of Drives & Alley Returns On 13th. St. Waco to Little Ark. River

City Of Wichita, Kansas
B.E. Smith City Engineer
Date Aug 1967 Proj. #7-106