B.M. 1349 Nail E. Side P. Pole, S. Amidon R/W on SL. 39th Street Extended.

NOTE:
Contractor to grade parkings & comp. fill for proposed sidewalk. Sidewalk to be constructed by others.
Depress Curb thru driveways.

0+58.12 | 1+00 | 1+50 | 2+00 | 2+50 | 3+00 | 3+50 | 4+00 | 4+50 | 4+88.73

-0.195% Roll Curb | 0.4 WK | -0.307%

End Roll Curb | 10' Curb Transition | 0.4 WK

Proposed Sidewalk

Roll Curb | Lip Cr. | Gutter Cr. | Lip Cr. | Roll Curb

L 20' Match

E. 1/2 Amidon Ave.

Sta. 0+80.12 (80.1' on Base Line)

0+55.12

E. 30' K.G. & C. Easement

-0.214% Roll Curb | 0.4 WK | -0.270%

10' Curb Transition

N

-0.02' + 1+91.93

E. 1/2 Woodrow Ave. Block 2 Plat

Δ = 90°05'10"
R. = 150.00'
L. = 117.75'

Δ = 90°05'10"
R. = 150.00'
L. = 118.05'

See plan of W. 1/2 Woodrow Ave., NL. 37th to NL. 39th for Curve Data.

NOTE:
All excavation to be used on W. 1/2 Woodrow Ave. from 37th St. No. to 39th St. No.

EXCAVATION	PROPERTY	CITY
	1,025 Cu.Yds.	21 Cu.Yds.
+10%	102 " "	2 " "
Totals	1,127 Cu.Yds.	23 Cu.Yds.
	1,930 Sq.Yds.	90 Sq.Yds. Cement Treated Sub-Grade.

COMP. FILL PROP.
8 Cu.Yds.
1 " "
9 Cu.Yds.

JAMES M. LINDY — LICENSED — 2012 — KANSAS — ENGINEER

R. W. LINN — LICENSED — 3584 — KANSAS — PROFESSIONAL ENGINEER

JOHN L. ALLEN — LICENSED — 821 — KANSAS — PROFESSIONAL ENGINEER

39th STREET NORTH.
WEST LINE SHERWOOD GLEN 2ND. ADDN. to E. L. LOT 6 BLOCK 1 SHERWOOD GLEN 2ND ADDN.
26-2-30 Asph. Conc.
R.W. LINN CITY ENGINEER
CITY OF WICHITA KANSAS
Date: July 1971
Project No. DAKS 5G5012

Clerk D.C.O. #36
Plan J.L.A.
Ck. "
Office "

11 5 1 (15)