

DIRECTORS
C. D. KNOX, P.E.
R. E. FREUND, P.E.
C. J. FREUND, P.E.
R. D. FLETCHER, P.E.
D. G. GILBERT, JR., P.E.
D. E. WALTERS, P.E.
W. D. SCHMIDT, P.E.
G. D. SCHMIDT, P.E.
J. H. BAILEY, P.E., M.D.

July 17, 1985

Sedgwick County Department of Public Works
1250 South Seneca
Wichita, Kansas 67213-4498

Attention: Mr. Jim Weber

Reference: Pine Bay Estates
Drainage Plan
PEC File No: 36-84032-959

Dear Mr. Weber:

As requested, we are transmitting herewith two (2) sets of calculations for the 100-year storm within the Wichita-Valley Center Floodway's Ponding Area "C".

As you can see, if the entire 100-year storm would be diverted from Ponding Area "C" to the existing lake in Pine Bay Estates, the Design Water Surface (DWS) would be approximately 1249.3 (MSL). This is about 0.8' higher than that calculated for the 25-year storm.

Also, the water depth in the control section of the overflow channel would be approximately 3.4'. This is 0.4' higher than the 25-year storm. Assuming the same section is used, the freeboard would be reduced from 3.0' to 2.6'.

If you have any questions or need any additional information, please call at your convenience.


Very truly yours,

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.

Charles S. Brown
Charles S. Brown, P.E.
Project Engineer

cc: Chris Breitenstein, P.E., Flood Control Engineer
Gerald Blood

CSB:kas



PROFESSIONAL
ENGINEERING
CONSULTANTS
P.A.



1240 EAST BOWLING
WICHITA, KANSAS 67211
(316) 262-2881



Date July 17, 1985 Page 1 of 4

Project Pine Bay Estates

Item Inflow to Big Ditch Ponding Area "C" (100 yr)

DA #1
 $A = 209 \text{ ac.}$
 $C = 0.35$
 $t_c = 2.00 \text{ hr (Avg.)} = 117 \text{ min.}$
 $t_{ro} = 2.35$
 $Q_{100} = 0.35 \times 2.35 \times 209$
 $= 172 \text{ cfs}$

DA #2
 $DA = 21 \text{ ac.}$
 $C = (49.4 \text{ ac.} \times 0.35) + (21.6 \text{ ac.} \times 0.3) = 0.34$
 $t_c = 0.2 \text{ min.}$
 $t_{ro} = 0.61$
 $Q_{100} = 0.34 \times 2.61 \times 121$
 $= 107 \text{ cfs}$

DA #3
 $DA = 130 \text{ ac.}$
 $C = 0.35$
 $t_c = 17 \text{ min.}$
 $t_{ro} = 2.35$
 $Q_{100} = 0.35 \times 2.35 \times 130$
 $= 107 \text{ cfs}$


PINE BAY ESTATES
(Drainage)



Date 7-17-85 Page 2 of 4

Project Pine Bay Estates

Item Inflow Hydrograph to Floodway Ponding Area "C" (100 yr)



Date July 17, 1985 Page 3 of 4

Project Pine Bay Estates

Item Inflow Hydrograph Ponding Area "C" (100 yr)

Time At	DA #1	DA #2	DA #3	Total
0	0	0	0	0
10	15	11	10	36
20	30	22	19	103
30	44	32	27	133
40	56	42	37	171
50	73	52	46	171
60	81	62	55	206
70	103	72	64	239
80	117	83	73	273
90	132	93	82	307
100	146	104	92	342
110	162	101	101	364
120	164	94	105	369
130	162	87	94	346
140	152	80	83	315
150	140	73	87	300
160	130	66	81	277
170	120	59	75	254
180	110	52	69	231
190	100	45	63	208
200	90	38	57	185
210	80	31	51	162
220	70	24	45	139
230	60	17	39	116
240	50	10	33	93
250	40	3	26	69
260	30	0	20	50
270	20	0	14	34
280	10	0	7	17
290	2	0	1	3
300	0	0	0	0



Date July 17, 1985 Page 4 of 4

Project Pine Bay Estates

Item Design Water Surfaces (100-yr)

1. Check DWS₁₀₀ in lake

Static Pool = 1246.20 MSL
Internal Drainage = 74.59 ac-ft = 0.28'
100-yr. Rainfall Directly on Lake = 7.9" = 0.66'
Drainage from Ponding Area "C" = 74.59 ac-ft = 2.16'
(External Drainage)
DWS₁₀₀ = 1249.30 MSL

2. Check DWS₁₀₀ in channel (emptying into lake)

Trapezoidal Shaped Weir

$Q = CLH^{3/2} + CZH^{3/2}$ where $Q = 375 \text{ cfs}$
 $375 = (30 \times 16 \times H^{3/2}) + (8.0 \times 4.0 \times H^{3/2})$
 $375 = 48 H^{3/2} + 32 H^{3/2}$
 $375 = 80 H^{3/2}$
 $H^{3/2} = 375/80 = 4.6875$
 $H = 6.25^{2/3}$
 $H = 3.39'$

Channel Provides 3' Freeboard - 25.4'
" 2.61' " 100-yr