



EROSION CONTROL MEASURE	UNITS	QUANTITY
Maintain Drop Inlet Barrier	Ea.	2
Maintain Straw Bale Ditch Check	Ea.	5
Maintain Silt Fence	L.F.	30
Maintain Ditch and Berm	L.F.	320
Maintain Construction Entrance	Ea.	1

Quantities are For Information Only! Contractor shall verify quantities per final bid quantity sheet.

Maintain Straw Bale Ditch Check Per Details, Sheets 15-18

Maintain 30 L.F. Silt Fence around Proposed Manhole

Maintain One Construction Entrance onto site per Details, Sheets 15-18

Maintain 320 L.F. Ditch and Berm

Maintain Straw Bale Ditch Check Per Details, Sheets 15-18

Maintain Drop Inlet Sediment Barrier Per Detail, SheetS 15-18

AUBURN HILLS 16TH ADD - PH 3
EROSION CONTROL PLAN
SANITARY SEWER IMPROVEMENTS

Baughman Company, P.A. 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149
 ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

<small>PROJECT NUMBER 448-90123</small>	<small>DESIGN AEG</small>	<small>DRAWN RDM</small>
<small>REVISIONS:</small>	<small>APPROVED RDM</small>	<small>DATE NOV 2007</small>
<small>SCALE NOTED</small>		12 OF 20
<small>SHEET</small>		

AuburnHills16th\Phase 3\WTR\Erosion Control Plan.dwg 07-09-E927