

RECAPITULATION OF BIDDING ITEMS

	(BC) 96-87 K-044-1(28) Pt. I		(BC) 96-87 K-044-1(28) Pt. II		(BC) 96-87 K-044-1(28) Pts. I & II	
BIDDING ITEMS	APPROXIMATE QUANTITIES	UNITS	APPROXIMATE QUANTITIES	UNITS	APPROXIMATE QUANTITIES	UNITS
REMOVABLE LEGEND SIGNS	1850.00	SQ. FT.	3290.00	SQ. FT.	5140.00	SQ. FT.
DIRECT SCREEN PROCESS SIGNS	471.34	SQ. FT.	143.56	SQ. FT.	614.90	SQ. FT.
REVERSE SCREEN PROCESS SIGNS	161.74	SQ. FT.	46.80	SQ. FT.	208.54	SQ. FT.
4"x6" WOOD POST (FOR FLAT SIGNS)	809.00	LIN. FT.	246.50	LIN. FT.	1055.00	LIN. FT.
4"x6" WOOD POST (FOR STRUCTURAL PANEL SIGNS)	285.08	LIN. FT.	226.20	LIN. FT.	511.28	LIN. FT.
312.5 ALUMINUM I-BEAM	15.00	LIN. FT.	60.00	LIN. FT.	75.00	LIN. FT.
2 LB PER FT "U" STEEL BEAM POST	22.00	LIN. FT.	22.00	LIN. FT.	44.00	LIN. FT.
3 LB PER FT "U" STEEL BEAM POST	24.00	LIN. FT.		LIN. FT.	24.00	LIN. FT.
	*A441	*A36(ALT)	*A441	*A36(ALT)	*A441	*A36(ALT)
53x5.7 STEEL BEAM POST	66.40	LIN. FT.	33.58	LIN. FT.	99.98	LIN. FT.
W6x8.5 STEEL BEAM POST	38.46	LIN. FT.	207.34	LIN. FT.	245.80	LIN. FT.
W10x11.5 STEEL BEAM POST	44.34	LIN. FT.	140.80	LIN. FT.	185.14	LIN. FT.
W10x21 STEEL BEAM POST	47.34	LIN. FT.	53.34	LIN. FT.	100.68	LIN. FT.
53x5.7 STEEL BEAM STUB POST	6.00	LIN. FT.	3.00	LIN. FT.	9.00	LIN. FT.
W6x8.5 STEEL BEAM STUB POST	4.00	LIN. FT.	24.00	LIN. FT.	28.00	LIN. FT.
W10x11.5 STEEL BEAM STUB POST	5.00	LIN. FT.	20.00	LIN. FT.	25.00	LIN. FT.
W10x21 STEEL BEAM STUB POST	6.00	LIN. FT.	6.00	LIN. FT.	12.00	LIN. FT.
6 1/2"x3"x3/4" BREAKAWAY BASE PLATE	4	EACH	2	EACH	6	EACH
6 1/2"x3"x3/8" BREAKAWAY BASE PLATE	4	EACH	2	EACH	6	EACH
9 3/8"x4 3/8"x1/8" BREAKAWAY BASE PLATE	2	EACH	12	EACH	14	EACH
9 3/8"x4 3/8"x3/8" BREAKAWAY BASE PLATE	2	EACH	12	EACH	14	EACH
13 3/8"x4 3/8"x1" BREAKAWAY BASE PLATE	2	EACH		EACH	2	EACH
13 3/8"x4 3/8"x3/4" BREAKAWAY BASE PLATE	2	EACH		EACH	2	EACH
14 3/8"x6 3/8"x1/8" BREAKAWAY BASE PLATE	2	EACH	2	EACH	4	EACH
14 3/8"x6 3/8"x1" BREAKAWAY BASE PLATE	2	EACH	2	EACH	4	EACH
18" DIA. CONCRETE FOOTING (STEEL POST)	20.00	LIN. FT.	10.00	LIN. FT.	30.00	LIN. FT.
24" DIA. CONCRETE FOOTING (STEEL POST)	34.00	LIN. FT.	84.00	LIN. FT.	118.00	LIN. FT.
30" DIA. CONCRETE FOOTING (STEEL POST)	24.00	LIN. FT.	24.00	LIN. FT.	48.00	LIN. FT.
18" DIA. CONCRETE FOOTING (WOOD POST)	222'	LIN. FT.	93'	LIN. FT.	315'	LIN. FT.
TYPE "A" WHITE DELINEATOR (8'-0" POST)	185	EACH	38	EACH	223	EACH
TYPE "A" WHITE DELINEATOR (7'-0" POST)	5	EACH	6	EACH	11	EACH
TYPE "A" WHITE DELINEATOR (6'-6" POST)		EACH		EACH		EACH
TYPE "A" YELLOW DELINEATOR (8'-0" POST)	50	EACH	18	EACH	68	EACH
TYPE "A" YELLOW DELINEATOR (7'-0" POST)		EACH	1	EACH	1	EACH
TYPE "A" YELLOW DELINEATOR (6'-6" POST)		EACH		EACH		EACH
TYPE "B" WHITE DELINEATOR (8'-0" POST)	42	EACH	66	EACH	108	EACH
TYPE "B" WHITE DELINEATOR (7'-0" POST)		EACH		EACH		EACH
TYPE "B" WHITE DELINEATOR (6'-6" POST)		EACH		EACH		EACH
TYPE "B" YELLOW DELINEATOR (8'-0" POST)		EACH		EACH		EACH
TYPE "B" YELLOW DELINEATOR (7'-0" POST)		EACH		EACH		EACH
TYPE "B" YELLOW DELINEATOR (6'-6" POST)		EACH		EACH		EACH
TYPE "C" YELLOW DELINEATOR (8'-0" POST)	4	EACH	2	EACH	6	EACH
TYPE "C" YELLOW DELINEATOR (7'-0" POST)	10	EACH	4	EACH	14	EACH
TYPE "C" YELLOW DELINEATOR (6'-6" POST)	2	EACH		EACH	2	EACH

RECAPITULATION OF BIDDING ITEMS

	(BC) 96-87 K-044-1(28) Pt. I		(BC) 96-87 K-044-1(28) Pt. II		(BC) 96-87 K-044-1(28) Pts. I & II	
BIDDING ITEMS	APPROXIMATE QUANTITIES	UNITS	APPROXIMATE QUANTITIES	UNITS	APPROXIMATE QUANTITIES	UNITS
REMOVAL OF STEEL I-BEAM POST	9	EACH	16	EACH	25	EACH
REMOVAL OF CONCRETE FOOTINGS	12	EACH	25	EACH	37	EACH
ADJUSTMENT OF LEGEND ON GUIDE SIGNS			LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM
OVERHEAD SIGN TRUSS MODIFICATION (54'-4 1/2') +35'+20'			1	EACH	1	EACH
CANTILEVER SIGN STRUCTURE (27'-0") STEEL			1	EACH	1	EACH
BRIDGE MOUNTED SIGN ATTACHMENT (36'-6") STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (51'-0") AL. OR STEEL	1	EACH			1	EACH
OVERHEAD SIGN STRUCT. (64'-0") AL. OR STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (84'-0") AL. OR STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (85'-0") AL. OR STEEL	1	EACH			1	EACH
OVERHEAD SIGN STRUCT. (90'-0") AL. OR STEEL	1	EACH	1	EACH	2	EACH
OVERHEAD SIGN STRUCT. (98'-0") AL. OR STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (99'-0") AL. OR STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (103'-0") AL. OR STEEL	1	EACH			1	EACH
OVERHEAD SIGN STRUCT. (109'-0") AL. OR STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (111'-0") AL. OR STEEL	1	EACH			1	EACH
TRAFFIC CONTROL	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM

* QUANTITIES AND PAYMENT FOR
STEEL BEAM POSTS AND FOOTINGS
The quantities for steel beam stubs, posts, and footings in the contract
are for the alternate A 36 steel.
When furnishing A 441 steel beam stubs, posts, and footings, payment
for these items will be based on A 36 steel unit prices and quantities included in
the contract.

3					
2					
1					
NO.	DATE	REVISIONS	BY	APP'D	
KANSAS DEPARTMENT OF TRANSPORTATION					
RECAPITULATION OF BIDDING ITEMS					
SHEET NO. 36 OF 143	SCALE NONE	APP'D	Lulu F. J.		
DESIGNED	QUANTITIES/DG	TRACED			
DESIGN CK.	DETAIL CK.	QUAN. CK.			