

CONC. PAVEMENT (9" UNIFORM)(AE)				
STATION TO STATION		SIDE	SQ. YDS.	REMARKS
KELLOGG ST.				
21+25.00	25+75.00	RT.	2400.00	EB-4 LANES
25+75.00	35+60.81	RT.	5267.20	EB-4 LANES
35+60.81	35+36.15	RT.	224.82	EB-BR. APP.
23+75.00	25+75.00	LT.	1066.67	WB-4 LANES
25+75.00	33+00.00	LT.	3857.12	WB-4 LANES
33+00.00	35+64.91	LT.	1059.64	WB-3 LANES
35+64.91	35+39.05	LT.	189.75	WB-BR. APP.
48+87.61	49+27.33	BL	137.88	RAMP NSW-BR. APP.
49+27.33	50+34.90	LT.	242.23	RAMP NSW
50+34.90	50+71.32	LT.	100.92	RAMP NSW
50+71.32	51+93.63	LT.	210.44	RAMP NSW
37+55.65	37+90.35	RT.	303.84	EB-BR. APP.
37+90.35	40+00.35	RT.	980.00	EB-3 LANES & TAPER
40+00.35	41+88.81	RT.	753.84	EB-3 LANES
41+88.81	42+23.47	RT.	188.85	EB-BR. APP.
37+58.55	37+93.42	LT.	189.75	WB-BR. APP.
37+93.42	41+92.01	LT.	1594.36	WB-3 LANES
41+92.01	42+26.03	LT.	188.85	WB-BR. APP.
52+62.97	52+96.99	RT.	188.85	EB-BR. APP.
52+96.99	61+63.07	RT.	3464.62	EB-3 LANE
61+63.07	61+99.90	RT.	198.22	EB-BR. APP.
52+65.53	53+00.19	LT.	188.85	WB-BR. APP.
53+00.19	59+50.86	LT.	2602.68	WB-3 LANES
59+50.86	61+60.86	LT.	980.00	WB-3 LANES & TAPER
61+60.86	61+70.86	LT.	40.00	WB-3 LANES
61+70.86	62+06.12	LT.	316.39	WB-BR. APP.
13+25.22	13+37.28	LT.	46.87	RAMP ENS
63+68.42	64+03.68	RT.	198.22	EB-BR. APP.
64+03.68	62+50.00	RT.	985.28	EB-3 LANES
50+82.11	51+27.18	BL	143.95	RAMP NSE-BW. APP.
51+27.18	52+40.65	LT.	270.53	RAMP NSE
52+40.65	53+77.68	LT.	235.31	RAMP NSE
66+50.00	68+00.00	RT.	797.30	EB-4 LANES
68+00.00	70+50.00	RT.	1163.00	EB-3 LANES & TAPER
70+50.00	73+85.91	RT.	1342.19	EB-3 LANES
73+85.91	74+00.00	RT.	75.15	EB-4 LANES
63+74.64	64+11.95	LT.	242.72	WB-BR. APP.
64+11.95	65+00.00	LT.	352.20	WB-3 LANES
10+00.00	10+87.55	LT.	122.24	RAMP ENS
65+00.00	66+00.00	LT.	533.33	WB-4 LANES
66+00.00	68+50.00	LT.	1169.45	WB-3 LANES & TAPER
68+50.00	69+15.26	LT.	261.79	WB-3 LANES
69+15.26	71+25.26	LT.	975.49	WB-3 LANES & TAPER
71+25.26	73+92.77	LT.	1070.62	WB-3 LANES
73+92.77	74+00.00	LT.	38.56	WB-4 LANES
GROVE ST. INTERCHANGE				
10+35.07	10+95.15	RT.	204.00	RAMP A TERMINAL
10+95.15	17+57.35	RT.	1325.06	RAMP A
17+57.35	18+49.40	RT.	204.41	RAMP A
18+49.40	21+14.86	RT.	602.28	RAMP A
10+40.48	11+13.48	LT.	239.88	RAMP B
11+13.48	20+36.18	LT.	1850.02	RAMP B
20+36.18	20+84.40	LT.	139.94	RAMP B
20+84.40	22+21.43	LT.	235.31	RAMP B
46+50.00	47+10.50	RT.	34.70	GROVE ST.
50+88.50	52+59.00	CL	334.67	GROVE ST.
325+43.95	330+13.41	CL	137.36	RT. SB 35W
325+44.66	330+13.10	CL	137.06	LT. NB 35W
INCLUDES PRESSURE RELIEF JOINTS				
EB FRONTAGE ROAD				
20+90.00	22+26.72	CL	423.86	
TOTAL				
			46,719.11	30,339.05

CONC. PAVEMENT (6" UNIFORM)(AE)							
STATION TO STATION		SIDE	SQ. YDS.	REMARKS			
WB FRONTAGE ROAD NO. 1							
21+18.47	25+10.45	C	1200.0				
WB FRONTAGE ROAD NO. 2							
66+07.15	71+20.66	C	1483.5				
GREEN ST.							
3+06.45	3+54.07	C	198.3	INCL. 2 FILLETS			
FRONTAGE ROAD "X"							
10+24.00	14+32.00	C	1229.0	INCL. 2 FILLETS			
EB FRONTAGE ROAD							
63+67.69	67+24.60	C	1036.3				
MAINTENANCE ROAD							
14+55.71	18+66.35	C	1000.6				
TOTAL			6147.7				
CONC. PAVT. (9" UNIFORM)(AE)(PLAIN)							
STATION TO STATION		SIDE	SQ. YDS.	REMARKS			
KELLOGG ST.							
10+06.06	25+75.00	LT	2919.5	LT. SIDE STA.*			
10+06.06	25+75.00	RT	6085.6	RT. SIDE STA.			
18+74	21+48	LT	108.9	REPLACE EX. MDN			
22+10	22+65	LT	20.9	REPLACE EX. MDN			
TOTAL			5925.1				
			129.8				
CONC. PAVEMENT (6" UNIFORM)(AE) ALLEY & ENTRANCE							
STATION	SIDE	LOCATION	WIDTH "W" FT.	DEPTH FT.	EXTEN- SION SQ. YDS.	AREA SQ. YDS.	ALLEY OR ENT.
21+46.1	LT.	WB F.R. NO. 1	26	15.5	10.3	47.6	ENT.
23+69.8	LT.	WB F.R. NO. 1	16	5.0	0	11.7	ALLEY
13+64.0	RT.	FR. RD. "X"	24	9.5	4.5	28.1	ENT.
13+97.0	RT.	FR. RD. "X"	20	9.5	4.5	23.9	ENT.
67+97.7	LT.	WB F.R. NO. 2	16	5.0	0	11.7	ALLEY
3+29.0	RT.	GREEN	7.5	14.5	7.0	18.3	ENT.
TOTAL							141.3
CONC. PAVT. (4" UNIFORM)(AE)(PLAIN)							
STATION TO STATION		SIDE	SQ. YDS.	REMARKS			
GROVE ST. MEDIAN							
46+50.00	47+10.50	RT.	38.0	INCL. NOSE			
50+88.50	52+59.00	CL	372.5	INCL. NOSE			
TOTAL			410.5				
MEDIAN FILLER MATERIAL							
STATION TO STATION		SIDE	TONS	REMARKS			
GROVE STREET MEDIAN							
46+50.00	47+10.50	RT.	27.9	INCL. NOSE			
50+88.50	52+59.00	CL	259.9	INCL. NOSE			
TOTAL				287.8			
				* 140 #/CU. FT.			

GUTTER (2'-10") (AE)				
STATION TO STATION	SIDE	LIN. FT.	REMARKS	
KELLOGG ST.				
35+64.91	36+00.85	LT.	35.94	WB
11+54.91	11+87.05	RT.	31.90	RAMP WNS
37+60.35	37+93.42	LT.	33.07	WB
41+88.81	42+21.89	RT.	33.08	EB
41+92.01	42+27.61	LT.	35.60	WB
52+61.39	52+96.99	RT.	35.60	EB
52+67.11	53+00.19	LT.	33.08	WB
61+63.07	61+96.01	RT.	32.94	EB
12+87.21	13+25.22	RT.	37.92	RAMP ENS
63+64.53	64+03.68	RT.	39.15	EB
TOTAL				
			348.28	
CONCRETE SAFETY BARRIER				
STATION TO STATION	SIDE	LIN. FT.	REMARKS	
KELLOGG ST.				
10+06.06	10+44.32	LT.	111.3	INCL. END SECT.
10+06.06	10+44.32	RT.	111.3	INCL. END SECT.
13+44.32	25+75.00	LT.	630.7	550' End Section
13+44.32	25+75.00	RT.	630.7	550' End Section
25+75.00	31+01.06	LT.	525.7	ON CURVE
25+75.00	31+01.06	RT.	526.4	ON CURVE
31+01.06	35+98.08	LT.	497.0	
31+01.06	35+97.12	RT.	496.1	
37+57.58	42+25.18	LT.	467.6	
37+56.62	42+24.32	RT.	467.7	
52+64.68	62+04.05	LT.	939.5	
52+63.82	62+01.97	RT.	938.2	
63+72.57	66+51.28	LT.	278.7	
63+70.49	66+51.28	RT.	280.8	
66+51.28	71+76.00	LT.	525.1	ON CURVE
66+51.28	71+76.00	RT.	524.4	ON CURVE
71+76.00	74+00.00	LT.	224.0	
71+76.00	74+00.00	RT.	224.0	
TOTAL				
			6485.2	7025.2
SIDEWALK CONSTRUCTION (4") (AE)				
STATION TO STATION	SIDE	WIDTH FT.	SQ. YDS.	REMARKS
WB FRONTAGE ROAD NO. 1				
21+15.5		RT.	5	81.3
21+15.5	21+86.00	LT.	5	27.0
21+86.00	25+10.45	LT.	5	168.6
WB FRONTAGE ROAD NO. 2				
66+07.15	66+21.00	RT.	4	10.7
66+07.15	66+33.5	LT.	4	6.8
66+33.5	69+45.00	LT.	5	151.2
69+45.00		LT.	4	10.6
70+05.5		LT.	4	18.9
70+05.5	71+20.66	RT.	5	63.0
EB FRONTAGE ROAD				
63+67.69		LT.	4	4.0
63+67.69	67+52.00	RT.	4	163.4
TOTAL				
			632.5	

STEEL PLATE GUARD FENCE				
STATION TO STATION		SIDE	LIN. FT.	REMARKS
KELLOGG ST.				
37+60.69	39+10.69	LT.	150.0	NE COR. BR. NO. 54-27.15
40+54.05	42+04.05	RT.	150.0	SW COR. BR. NO. 54-27.33
52+84.95	54+34.95	LT.	150.0	NE COR. BR. NO. 54-27.34
60+45.65	61+95.65	RT.	150.0	SW COR. BR. NO. 54-27.62
32+43.58	35+93.58	RT.	150.00	SW COR. BR. NO. 54-27.14
63+80.21	65+30.21	LT.	150.00	NE COR. BR. NO. 54-27.63
71+92.5	73+66.85	LT	175.00	
TOTAL			1375.0	
20+75		23+45	LT. 215.0	NE COR. PED. OVERPASS
1350.0				
REMOVAL OF STEEL PLATE GD. FC.				
STATION TO STATION		SIDE	LIN. FT.	REMARKS
EB KELLOGG (US 54) DETOUR				
43+99.01	45+49.01	LT.	150	WEST END BR. NO.
43+99.01	45+49.01	RT.	150	35W-87-14.35
WB KELLOGG (US 54) DETOUR				
51+93.30	53+43.30	LT.	150	EAST END BR. NO.
51+93.30	53+43.30	RT.	150	35W-87-14.56
22+82.5	23+45	LT	62.5	W FRONTAGE RD
TOTAL			662	

REVISED PLANS

COMBINED CURB & GUTTER						
STATION TO STATION	SIDE	TYPE I LIN. FT.	TYPE II LIN. FT.	TYPE III LIN. FT.	TYPE III(SPE.) LIN. FT.	REMARKS
KELLOGG ST.						
10+49.32	25+75.00	LT	630.38			RT. EB
25+75.00	35+93.87	RT.	1022.15			RT. EB
21+25.00	25+75.00	RT.	450.00			RT. EB
10+49.32	25+75.00	LT	627.94			LT. WB
25+75.00	33+00.00	LT.	721.82			LT. WB
23+75.00	25+75.00	LT	200.00			LT. WB
48+86.25	50+67.30	RT.	181.05			RAMP NSW
50+67.30	51+93.63	RT.	125.30			RAMP NSW
50+79.10	53+77.68	RT.	296.65			RAMP NSE
66+50.00	68+00.00	RT.	149.10			EB
68+00.00	70+50.00	RT.	248.79			EB
70+50.00	71+38.35	RT.	147.89			EB
73+85.91	75+00.00	RT.	114.09			EB
10+00.00	11+20.48	RT.	120.15			RAMP ENS
65+00.00	66+00.00	LT.	100.00			WB
66+00.00	68+50.00	LT.	251.29			WB
68+50.00	71+12.36	LT.	264.02			WB
73+92.77	74+00.00	LT.	7.23			WB
GROVE ST. INTERCHANGE						
10+23.93	10+95.15	LT.	93.84			RAMP A RET.
10+95.15	21+14.86	LT.	1019.02			RAMP A
10+44.74	10+51.23	RT.	16.58			RAMP A RET.
10+51.23	10+68.12	RT.			16.45	RAMP A RET.
10+68.12	17+04.47	RT.			636.35	RAMP A
17+04.47	18+36.08	RT.			133.39	RAMP A
10+21.12	10+86.04	RT.	80.01			RAMP B RET.
10+86.04	17+91.27	RT.	705.23			RAMP B
17+91.27	22+21.43	RT.	429.13			RAMP B
10+69.55	10+70.80	LT.	13.92			RAMP B RET.
10+70.80	11+13.48	LT.			47.77	RAMP B RET.
11+13.48	17+91.27	LT.			677.79	RAMP B
11+91.27	20+36.18	LT.			249.85	RAMP B
GROVE ST.						
45+68.50	46+47.50	LT.	79.00			SB
51+57.00	52+12.50	LT.	55.50			SB
46+02.37	46+37.00	RT.	34.63			NB
51+62.50	52+47.50	RT.	35.00			NB
46+50.00		RT.		9.42		MED. NOSE
46+50.00	47+10.50	RT.		60.40		NB MED.
46+50.00	47+10.50	RT.		60.47		SB MED.
50+88.50	52+59.00	RT.		170.50		NB MED.
50+88.50	52+59.00	LT.		170.50		SB MED.
52+59.00		CL		28.27		MED. NOSE
ENTRANCE REPLACEMENT						
N. SIDE OF MADISON & N. OF OSIE		120				5 ENT.
N. SIDE OF GILBERT & E. OF MADISON		30				1 ENT.
N. SIDE OF SPRUCE S. OF ORME		48				3 ENT.
N. SIDE OF VOLUNTIA S. OF F.B. FR. RD.		32				1 ENT.
SIA. 5+23.10 SIA. 5+43 F. FR. RD. "X"		20				1 ENT.
TOTALS		250.00	-	499.56	1761.60	

7267.39