

Ironwood Circle

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
10+50.00	0.00	56.94	0.00	51.53	0.00	51.53
10+75.00	0.00	54.37	0.00	51.83	0.00	103.36
11+00.00	0.00	57.58	0.00	55.23	0.00	158.59
11+25.00	0.00	61.71	0.00	59.15	0.00	217.74
11+50.00	0.00	66.05	0.00	63.17	0.00	280.91
11+75.00	0.00	70.39	0.00	30.56	0.00	311.47
11+86.57	0.00	72.25	0.00	36.47	0.00	347.94
12+00.00	0.00	74.41	0.00	141.76	0.00	489.70
12+50.00	0.00	78.69	0.00	143.82	0.00	633.52
13+00.00	0.00	76.64	0.00	19.44	0.00	652.96
13+06.88	0.00	75.97	0.00	50.65	0.00	703.61
13+25.00	0.00	74.96	0.00	69.04	0.00	772.65
13+50.00	0.00	74.16	0.00	27.96	0.00	800.61
13+60.18	0.00	74.17				

The Pines at Sawmill Creek, Paving Improvements Earthwork Quantities WICHITA, KANSAS			
	Ruggles & Bohm, P.A. Engineering, Surveying, Land Planning		DESIGN <i>AML</i>
	924 North Main Wichita, Kansas 67203 www.rbkansas.com		(316) 264-8008 (316) 264-4621 fax E-mail: info@rbkansas.com
DRAWING FILE <i>Paving {xsec-quant}</i>		PROJECT NUMBER 472-84630	DATE Jan. 22, 2008
			RB JOB J3AE
			SHEET 12 OF 15