

EARTHWORK SUMMARY

STREET	CUT CU. YDS.	LOOSE FILL CU. YDS.	COMPACTED FILL CU. YDS.
** TRIPLE CROWN	130	1075	4422
** MUSTANG ST./CIR.	515	757	1433
** MUSTANG CT.	13	712	181
** EQUESTRIAN CIR.	0	731	2850
** EQUESTRIAN ST./CIR.	2317	217	283
** EQUESTRIAN CT.	206	323	192
	<u>3181</u>	<u>3724</u>	<u>9361</u>
15% SHRINKAGE		559	1404
STREETS TOTAL	3181	4283	10765
SITE			
** RESERVE C	1581	3855	0
** RESERVE E	3312	195	0
RESERVE E	39520	1368	0
** BLOCK 2	917	25401	0
** BLOCK 6	10106	7230	0
	<u>55436</u>	<u>38049</u>	<u>0</u>
8% SHRINKAGE		3044	0
SITE TOTAL	55436	41093	0
PROJECT TOTALS	58617	45376 •	10765 •

* LOOSE FILL AND COMPACTED FILL SHALL NOT EXCEED EXCAVATION
(2,476 CY WILL BE WASTED ON SITE - SEE LOT GRADING PLAN)

** FROM COMPANION STREET PROJECT

FINAL

Designed By: JMU/JPD
 Drawn By: JMU/JPD
 Pce Job No.: 1694J
 Date: January 2006



POE & ASSOCIATES, INC.
 CONSULTING ENGINEERS
 5940 E. Central, Suite 200 ■ Wichita, KS 67208-4242
 Phone 316/685-4114 ■ FAX 316/685-4444

EQUESTRIAN ESTATES ADDITION - PHASE 2
 STORM WATER DRAIN NO. 179
 EARTHWORK SUMMARY
CITY OF WICHITA, KANSAS
 JAMES L. ARMOUR, P.E. - CITY ENGINEER
 C.O.W. Project # 488-83319 O.C.A. # 75140

No.	Date	By	Approved	Revision
△				
△				
△				
△				