


STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
9+53.38	38.38	7.53				
9+94.85	47.17	5.28	65.04	11.56	65.04	11.56
10+00	48.23	4.92	9.10	0.97	74.14	12.54
10+50	54.05	1.79	94.71	6.22	168.85	18.76
11+00	54.69	0.54	100.69	2.16	269.53	20.92
11+50	54.15	0.71	100.78	1.17	370.31	22.09
12+00	52.12	1.12	98.40	1.70	468.71	23.78
12+50	48.53	2.33	93.19	3.19	561.91	26.98
13+00	40.50	7.68	82.43	9.26	644.34	36.24
13+50	39.84	7.97	74.38	14.48	718.72	50.73
13+70	39.15	14.08	29.25	8.17	747.98	58.89
14+00	24.68	22.62	35.46	20.39	783.44	79.28
14+50	15.38	30.09	37.09	48.80	820.53	128.09
14+81.83	10.69	34.93	15.37	38.33	835.90	166.41
15+00	7.98	38.85	6.42	23.77	842.32	190.18
15+50	1.12	60.15	9.22	87.18	851.54	277.36
16+00	0.00	91.45	1.12	133.31	852.66	410.67
16+38.91	0.54	71.55	0.43	110.58	853.09	521.24
16+50	0.92	66.11	0.30	28.27	853.39	549.52
17+00	5.20	44.73	5.67	102.63	859.06	652.15
17+50	11.35	34.63	15.33	73.48	874.39	725.63
18+00	19.73	26.18	28.78	56.31	903.17	781.94
18+50	25.35	21.58	41.74	44.22	944.91	826.16
18+74.92	25.91	19.03	23.66	18.74	968.57	844.90
19+00	30.67	14.16	26.11	16.29	994.68	861.19
19+38.82	41.22	4.93	51.38	15.62	1046.06	876.81
19+50	42.27	4.84	17.15	2.48	1063.21	879.29
20+00	41.30	7.94	76.83	14.43	1140.03	893.72
20+32	41.34	8.36	48.74	11.32	1188.77	905.04
20+50	41.87	7.73	27.73	5.36	1216.50	910.41
20+74	43.39	5.13	37.89	5.72	1254.40	916.12
			0.00	0.00	1254.40	916.12

Fawn Grove at Sunset Lakes Phase 3
Cross Section Quantities
WICHITA, KANSAS



Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main (316) 264-8008
Wichita, Kansas 67203 (316) 264-4621 fax
www.rbkansas.com E-mail: info@rbkansas.com

DESIGN E.J.G.	SHEET 23 OF 24
DRAWN E.J.G.	
REVIEW	
UTILITY	
DRAWING FILE Paving {Fawn Grove}	PROJECT NUMBER 472-84408
DATE April 27, 2006	