BARTLOW DRIVE

ST. 80.

40'

30'

120.87'

BARTLOW 10

V.L. Dart-on

NOTE: TO CONTRACTOR
Replace fences
Replace 4" conc. retaining wall

NOTE: Save 4" Cedar tree

4

800'

N.L. ADDN. DIST.

ADDN.

200'

Prop. Iron

4" Cedar

4" Conc. ret. wall

3" Conc. Ret. wall

3" Sewer to P.O.

Power Pole

8"

Prop. Iron

130'

14.5'

12.5'

E. Rim 87.69
Flo 81.38

Prop. Phone Water Gas Manh.

G.E.P.

RESERVE.

STA. 0+00
EXIST. M.H.

STA. 1+76
END 8" V.C.P.
"PLUG PIPE"

317'±

Flo 81.38

40'

Plan Scale 1"=40'
Profile Scale 1"=40' Hor.
1"=4' Vert.

B.M. 86.31 R.R. Spike N.S. P.P.W. side Midland Valley R.R. & S.S. 63 rd ST. SO.

90'

80'

70'

Nat. Gro.

Sand Fill or Flush

8" V.C.P. @ 0.20%

STA. 0+00
EXIST. M.H.

STA. 1+76
END 8" V.C.P.
PLUG PIPE

Flo Enter. 15" 81.87
Flo In 8" 82.18

82.55

82.50 Flo

82.55

176 LIN FT. 8" V.C.P. @ 0.20% GRADE

LAT. 5, GLENVILLE SEWER
CITY OF WICHITA, KANSAS
B.E. SMITH, CITY ENGINEER
PROJECT NO. C26-64
DATE: FEB. 1967

Flo 116.63

ST.

802.40'

29 TH

Asphalt

Curb & Gutter

20 JONES PARK

21

22

23

24

25

26

27

28

24

Kans Club

Septic tank

30" S.W.S.

20' patrol easem't

Walk

Gravel parking lot

Hedge

House

STA. 0+00 CONST.
STD. M.H. TYPE "A"
STUB NE & NW

STA. 1+40 CONST.
STD. M.H. TYPE "A"
CONST. 4" STUB NE & NW

125'

25'

25'

ADDN.

19

18

17

10

FAIRVIEW AVE.

Flo 116.52

B.M. 129.102 City B.M. disc. S.E. cor. 29th & Arkansas

Plan Scale 1"=20'
Profile Scale 1"=20' Hor.
1"=9' Vert.

NOTE: TO CONTRACTOR
Replace asphalt in 29th St. with 2" Asphaltic conc.
Replace gravel in parking lot with same as exist.
4" stubs to be included in Bid price of Lin Ft. 8" V.C.P.

130

120

110

STA. 0+00 CONST.
STD. M.H. TYPE "A"
CONST. 4" STUB NE & NW
Flo 116.52

STA. 1+40 CONST.
STD. M.H. TYPE "A"
CONST. 4" STUB NE & NW
Flo 110.28

Gravel Parking lot

Sand Fill or Flush

30" S.W.S. (exact depth unknown)

8" V.C.P. @ 1.00% GRADE

Excav. 32 cu. yds. 116.55
Fill 32 cu. yds. 112.68

119.88

Flo 110.28

140 LIN FT. 8" V.C.P. @ 1.00% GRADE

LAT. 64, SUB. 9, S.S. 23.
CITY OF WICHITA, KANSAS
B.E. SMITH, CITY ENGINEER
PROJ. NO. C26-71
DATE: AUG. 1967

0 1 2

3 13 2 (S)