BARTLOW DRIVE

ST. 80.

BARTLOW 10

NOTE: TO CONTRACTOR
Replace fences
Replace 4" conc. retaining wall

NOTE: Save 4" Cedar tree

ADDN.

RESERVE.

STA. 0+00 EXIST. M.H.

STA. 1+76 END 8" V.C.P. "PLUG PIPE"

Plan Scale 1"=40'
Profile Scale 1"=40' Hor.
1"=4' Vert.

B.M. 86.31 R.R. Spike N.S. P.P. W. side Midland Valley R.R. & S.S. 63rd ST. 50.

STA. 0+00 EXIST. M.H.

STA. 1+76 END 8" V.C.P. "PLUG PIPE"

Nat. Gro.

Sand Fill or Flush

8" V.C.P. @ 0.20%

176 LIN FT. 8" V.C.P. @ 0.20% GRADE

LAT. 5, GLENVILLE SEWER
CITY OF WICHITA, KANSAS
B. E. SMITH, CITY ENGINEER
PROJECT NO. C26-64
DATE: FEB. 1967

JONES PARK

Kans Club

Gravel parking lot

Hedge

House

ADDN.

FAIRVIEW AVE.

STA. 0+00 CONST. STD. M.H. TYPE "B"

STA. 1+40 CONST. STD. M.H. TYPE "B" CONST. 4" STUB NE & NW

Plan Scale 1"=20'
Profile Scale 1"=20' Hor.
1"=4' Vert.

NOTE: TO CONTRACTOR
Replace asphalt in 29th St. with 2" Asphaltic conc.
Replace gravel in parking lot with same as exist.
4" stubs to be included in Bid price of Lin Ft. 8" V.C.P.

B.M. 129.102 City B.M. disc. S.E. cor. 29th & Arkansas

Gravel Parking lot

Sand Fill or Flush

80° S.W.S. (exact depth unknown)

8" V.C.P. @ 1.00% GRADE

140 LIN FT. 8" V.C.P. @ 1.00% GRADE

LAT. 64, SUB. 9, S.S. 23.
CITY OF WICHITA, KANSAS
B. E. SMITH, CITY ENGINEER
PROJ. NO. C26-71
DATE: AUG. 1967