

BENCHMARKS:

"□" CUT ON TOP OF NORTH CURB APPROX 8.2' NW OF NW EDGE OF DRIVEWAY ON LOT 8, BLOCK 2
ELEV. = 156.20'
"□" CUT ON TOP OF CURB AT N END OF N CURB RETURN AT INTERSECTION OF RAINBOW LAKES AND RAINBOW LAKES CT.
ELEV. = 156.82

RAINBOW LAKES WEST ADDITION

Contractor to protect street sign during construction. Remove/Reset as necessary. Cost incidental to "Site Clearing & Restoration".

Saw, Remove & Replace 8 L.F. Concrete w/ Curb & Gutter to Limits as Shown. Replace w/ 7" Valley Gutter Concrete over 6" Rein Crushed Rock Base

CAUTION!
Ex. U/G Cable TV.

CAUTION!
Ex. U/G AT&T.

CAUTION!
Ex. U/G AT&T.

0 10 20
SCALE:
1" = 20' Horizontal
1" = 5' Vertical

