LOCATION
- LOT 1 EVC ADDITION WICHITA, SEDG. CO.
- PROJ. ADDRESS 4110 S. WEBB ROAD WICHITA, KS.

OCT. 31, 1980
CONTRACTOR
DON VAUGHN

NOTE TO CONTRACTOR
This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will reimburse the City of Wichita for all cost of [redacted] Inspection.

10-31-80

APPROVED AS NOTED
By CITY ENGINEER OF WICHITA
Sanitary Sewers D.C.H.
Storm Sewers
Driveway Approaches

PLAN
SURVEYED
PLOTTED
NOTE BOOK
NO.
DRAWN
ALIGNMENT CHECKED
R/W CHECKED
BY
DATE

GRANT OF EASEMENT FILM 360 PAGE 263 EXHIBIT "A"

110 FT. 8" MAIN W/ (1) MAN HOLE

EXIST. SANITARY SEWER M.H. TOP OF RING 172.55

NORTH

THE RESIDENCE INN
LOT 1 EVC ADDITION
WICHITA, SEDGWICK CO., K.S.
SCALE: 1"=30'

CAST IRON M.H. COVER
GROUT BETWEEN M.H. RING & SECTION
22" MIN
CONCENTRIC SECTION
TYPE A OR TYPE C
4'-0" MIN
CLASS B 3000 PSI CONC.
10"
GROUT
8" THICK BASE W/ 12" REBAR ON 6" CENTER
8"

MANHOLE DETAIL NO SCALE

PROFILE
SURVEYED
PLOTTED
NOTE BOOK
NO.
DRAWN
H & V NOTED
STRUCTURE NOTATIONS CHECKED
BY
DATE

20' UTILITY EASEMENT

KELLOGG

SANITARY SEWER DETAIL NOT AS LOCATED

SEWER CONSTRUCTION
CONSULTING ENGINEERS
ROOM 310 AM 2-7881
MIRAMAR, WICHITA

PLATE 1 - PLAN - PROFILE - F.A.S.
CLEARPRINT PAPER CO., S.F. CAL.
NO. 1152H-1

Project # 468-76-245-80000-000-000-008

FILMED FROM THE BEST