



Scale: 1" = 60'

Maintain End-of-Road Straw Bale Sediment Barriers. See Detail, Sheet 11.

Contractor to Maintain one Construction Entrance onto Existing Paved Roadway, per Detail Sheet 16.

Maintain / Remove & Replace Existing Straw Bale Ditch Checks

Restore Existing Temporary V-Ditch to Ensure Proper Drainage of Sump Areas Following Water Line Installation per Detail, Sheet 9. (Cost Incidental to "Site Clearing & Restoration")

Maintain 40 L.F. Existing Silt Fence

EROSION CONTROL PLAN LEGEND
(Installation Details Found in the SWP2 Plan)

- DROP INLET PROTECTION
- CURB INLET PROTECTION
- DITCH CHECKS
- SILT FENCING
- CUT-OFF TRENCH
- BACK OF CURB PROTECTION
- EROSION CONTROL MAT
- TEMPORARY DITCH

NO SCALE

	Silverton Addition - Phase II	
	EROSION CONTROL PLAN	
Water Distribution System		
<small>Baughman Company, P.A. 315 Ellis St. Wichita, KS 67211 P 316-262-7771 F 316-262-0149 ENGINEERING SURVEYING PLANNING LANDSCAPE ARCHITECTURE</small>		
PROJECT NUMBER 448-90239	DESIGN JAK	DRAWN JAK
REVISIONS:	APPROVED	DATE 4/29/08
	SCALE Noted	
	SHEET	8 OF 17

Silverton\Phase 2\Wtr_Erosion.dwg