



ASPHALT PAVEMENT		
LOCATION	ASPHALT (5") (SY)	REMARKS
STATION TO STATION		
10+35.99 to 16+29.43	1714.75	
TOTAL	1714.75	

CRUSHED ROCK BASE		
LOCATION	CRUSHED ROCK BASE (5") (SY)	REMARKS
STATION TO STATION		
10+13.84 to 16+29.43	2380.42	
TOTAL	2380.42	

SEEDING			
ITEM	QUANTITY	UNITS	REMARKS
TOTAL SEEDING	0.37	ACRE	

EXCAVATION / COMPACTION			
LOCATION	CUBIC YARDS		REMARKS
	CUT	FILL	
STATION TO STATION			
TOTAL	979.36	119.93	

CURB AND GUTTER		
LOCATION	6" CURB 2.50' GUTTER (LF)	REMARKS
STATION TO STATION		
10+35.99 to 12+94.29	258.30	10th (North Side)
10+36.70 to 10+88.36	51.66	10th (South Side)
11+24.36 to 12+10.77	86.41	10th (South Side)
12+46.77 to 14+44.00	197.23	10th (South Side)
13+65.29 to 14+44.00	78.71	10th (North Side)
14+56.00 to 15+15.15	59.15	10th (South Side)
14+56.00 to 16+17.29	161.29	10th (North Side)
15+39.15 to 16+16.73	77.58	10th (South Side)
TOTAL	970.33	

VALLEY GUTTER		
LOCATION	REINFORCED CONCRETE (8") (SY)	REMARKS
Q STATION		
10+13.84	103.07	Start (St. Paul)
13+30.08 13.00 Rt	105.12	Intersection at Gordon (North)
TOTAL	208.19	

MONOLITHIC CURB		
LOCATION	6" CURB 2.50' GUTTER (LF)	REMARKS
STATION TO STATION		
10+13.49 to 10+35.99	32.00	10th and St. Paul (Northeast Side)
10+14.20 to 10+36.70	32.40	10th and St. Paul (Southeast Side)
12+94.29 to 13+14.79	32.37	10th and Gordon (Northwest Side)
13+44.79 to 13+65.29	32.62	10th and Gordon (Northwest Side)
TOTAL	129.39	

STORM WATER SEWER			
ITEM	QUANTITY	UNITS	REMARKS
15" RCP	37.00	LF	
24" RCP	174.05	LF	
4' Spcl. Shallow MH	1	EA	
Type 2 Inlet (sgl)	2	EA	

RECAPITULATION OF ROAD QUANTITIES		
ITEM	QUANTITY	UNITS
Asphalt Pavement	1714.75	SY
Crushed Rock Base	2380.42	SY
Curb and Gutter	970.33	LF
Monolithic Curb	129.39	LF
Valley Gutter	208.19	SY
Concrete Driveways	150.67	SY
Inlet Hook-ups	4	EA
Curb Replacement	15.00	LF
Sawed Joint	136.26	LF
15" Re-Inforced Concrete Pipe	37.00	LF
24" Re-Inforced Concrete Pipe	174.05	LF
4' Special Shallow Manhole	1	EA
Type 2 Curb Inlet (Single)	2	EA
Pavement Removal (w/ Mono. Curb)	157.74	SY
Comb. Curb & Gutter Removed	15.00	LF
Curb Inlet Removal	2	EA
Trees, Large Removed	1	EA
Site Clearing & Restoration	1	LS
Seeding	1	LS
Excavation (Cut)	979.36	CY
Excavation (Fill)	119.93	CY
Sediment Barrier, Inlet	4	EA
Back of Curb Protection (8' Wide)	1181.55	LF
Decorative Block Retaining Wall	10	LF

**10th Street Improvement  
Cross Sections  
Wichita, Kansas**

PROJECT NUMBER  
**472-84454**

	KEW NO. 07078	FILE x-section	DATE 1/2008	SHEET 14
	DESIGN KM	DRAWN NS	REVISED	OF 14

516 S. Market, Wichita, KS 67202      316/264-0242