ROCK ROAD

BM 1145.41 Chisled "x" top of Handrail @ West end of Triple 8'x8' RCB on Harry approx. 250' E. of Rock Road.

119' | 128.49' | 56.25' | 100.53' | 55.75'

124.25 to N.L. Harry St.

Lot 12, Main 16, War Ind. Sewer

250' | 250' | 240'

1 0.483 Ac. | 2 0.737 Ac. | 3 1.192 Ac.

ADDN.

Ex. Manhole, 89.6' Lt., Fl. 130.69

Constr. Manhole Sta. 0+00

20' Utility Easement

Constr. Manhole Sta. ~~1+80~~ 2+20

Constr. Manhole Sta. ~~4+45~~ 3

119' | 128.49' | 212'

229.49' | 230'

Constr. 8" San. Sewer | Constr. 8" San. Sewer | 6" Stubs E & W

8" | 8" | 8"

328.70'

Ex. Manhole, 182.35' Rt. Fl. 131.98

LAT. 13, MAIN 16, WAR IND. SEWER

Sta. 4+85.95

SCALE: 1"=40'

BRANSON

4 1.697 Ac. | 5 1.196 Ac.

321.42' | 321.15'

199.49 | 230'

31.4'

LONGFELLOW

PLAN

DSC-112 (Lewis) W.S.K.

Rec. p. 199, Bk 23

PROFILE

Sta. 0+00 Constr. Std. Type or 'C' Manhole	Sta. 2+20 Constr. Std. Type or 'C' Manhole	Sta. 4+45 Constr. Std. Type or 'C' Manhole
155		
150		
145		
140		
135		
130		
Ex. 8" N. 131.12		
133.18	134.00	134.80
133.18	133.92	134.72

t.c. Curb Longfellow

Existing Ground

℄ Proposed & Rock Road

LAT. 13, MAIN 16, WAR IND. SEWER

645' of ~~Std. Strength~~ Pipe @ +0.40%

Alternate SDR 35 P.V.C. Composite Pipe

0 | 1 | 2 | 3 | 4 | 5

PLATE 1-SINGLE PLAN AND PROFILE-FULL LINE

DONALD L. SCHNEIDER, 6311, KANSAS, PROFESSIONAL ENGINEER

As Built 6-28-77

LAT 13, MAIN 16, W.I.S.
CITY OF WICHITA, KANSAS
R.W. LINN-CITY ENGINEER
Project DBKL 575080
DATE June 1977 Sheet 1 of 1

14 10 4 2 1/1