CHERRY CREEK HILLS

CHERRY CREEK DRIVE

AVE.

ROCK ROAD

PAWNEE

DM 1165.71 "+" on Center Line Rock Road & Center of Pawnee West.

SCALE: 1"=40' PLAN 1"=40' Horiz. PROFILE 1"=5' Vert.

NOTE: CONSTRUCTION OF THIS PROJECT SHALL BE COORDINATED WITH MAIN SEWER CONSTRUCTION ALONG THE EAST SIDE OF ROCK ROAD.

Sta 10+45.5 Const. Std. MH Type "A" Install 8"-Stub NE & Ea 160.40 Install 8"-Stub SE & Ea 162.50

Sta 10+02.5 Existing MH w/ 8"-Stub E Beyond 8"-Line E.

Sta 9+02.5 Const. Std. MH Type "A"

Sta 8+57.5 Const. Std. MH Type "A"

Sta 7+42.5 Const. Std. MH Type "A"

Sta 6+27.5 Const. Std. MH Type "A"

Sta 5+12.5 Const. Std. MH Type "A"

170
165
160
155
150

1165.5 Lin Ft 8" Clay Pipe @ 9%

AS BUILT Feb. FLOW 280 Y

Lat. 1, Main 17, W.I.S.
R.W. LINN City Engineer
City of Wichita, Kansas
Date: July 1973
Project No. DBKL 573012