B.M.= 184.60 ~ R.R. Spike Top 2' guard post, E. side Webb Rd approx. 100' N. of N.L. Bedell W.
B.M.= 176.15 ~ Iron in thimble ¼ Sec. Cor. Lincoln & Webb Rd.

Sta 2+95 Constr. Std. Type "A" Manhole "4" 8" Stub East.

Proposed 8" San. Sewer

Exist. 20' Easmt.

Exist. 15' Easmt.

Exist. 10' Easmt.

Exist. 16' Easmt.

Proposed 10' Easmt.

Sta 5+43 Constr. Std. Type "A" Manhole

Sta 6+63 Constr. Std. Type "A" Manhole

Sta 8+45 Constr. Std. Type "A" Manhole (Part of Proposed Quail Meadows Third Addn)

Sta 9+60 Constr. Std. Type "A" Manhole

QUAIL MEADOWS FIRST ADDN.

(Not in Benefit District.)

NORTH

ST.

LINCOLN CT.

LINCOLN

½ Sec. Line 3

Part of Lot 1, Blk 1, Quail Meadows First Addn. (Not in Benefit District)

Exist. 15' Easmt.

Sta. 0+00 Exist. MH. (1055.2 M-18) Connect to Exist. 8" Stub.

Proposed MH & 8" San. Sewer

Proposed A.C. Pvmt

Pvmt Comb. C&G Str.

Scale:
Plan: 1"=40'
Profile: Horiz.: 1"=40'
Vert.: 1"=5'

Sta 0+00 Exist. Manhole Connect to Exist. 8" Stub

Sta 2+95 Constr. Std. Type "A" Manhole by 8" Stub E.

Sta 5+43 Constr. Std. Type "A" Manhole

Sta 6+63 Constr. Std. Type "A" Manhole

Sta 8+45 Constr. Std. Type "A" Manhole

Sta 9+60 Constr. Std. Type "A" Manhole

Proposed Top of Curb W. Side Beech

Proposed Top of Curb Lincoln Ct.

157.80

295 L.F. 8" Clay Pipe @ 1.08%

368 L.F. 8" Clay Pipe @ 1.06%

297 L.F. 8" Clay Pipe @ 2.12%

0+00 Fl. 150.79 Out - 10" Fl. 150.99 In - E 6" Fl. 150.74 In - E 6"

2+95 — Fl. 156.51 Out Fl. 156.81 In - 6" Stub E. Fl. 156.61 In - S.

5+43 Fl. 159.24 Out Fl. 159.34 In

6+63 Fl. 160.81 Out Fl. 160.71 In

8+45 Fl. 164.57 Out Fl. 164.67 In

9+60 Fl. 167.11

Fl. 152.44 — Fl. 154.12 — Fl. 157.72 — Fl. 158.19 — Fl. 159.94 — Fl. 161.50 — Fl. 163.62 — Fl. 165.83

0 1 2 3 4 5 6 7 8 9

175 170 165 160 155 150

LARRY W. LAURSEN LICENSED 6363 KANSAS PROFESSIONAL ENGINEER

LAT. 2, MAIN 18, W.I.S.
CITY OF WICHITA, KANSAS
R.W. LINN - CITY ENGINEER
DATE: PROJ. NO. DBKL574012

FILMED FROM THE BEST