B.M. 104.29 City Disc 52'N.+ 44'E & Hillside + 31st South
B.M. 99.14 "X" cut on N.W corner of Lower step on W-side of Bldg.

Plan Scale 1" = 40'
Profile Scale 1" = 40' Hor.
1" = 5' Vert.

Benefit District Line

Ground Elev. 103.1
4" line, East
of West 97.21

4'x6' septic tank

"Casino" Bldg

Unplated tract C22240

1711.0
Sta 1+07
Const Std. M.H.
Type 'A' or 'C'

1757.7
Sta 1+61
Const Std. M.H.
Type 'A' or 'C'
Install 4" Stub South
End Project

375'

31ST ST. SOUTH

Note: Take ties & Replace Iron

Burial Cable S.W.B.

Lot 14

Sta 0+00
Exist. M.H. (No Stub)
Begin 8" Pipe

Lot 11

Lot 10

Addition

Edminister

[NOT IN BENEFIT DISTRICT]

HILLSIDE

NOTE: TRAFFIC SHALL BE CARRIED THROUGH CONSTRUCTION ON 31ST STREET SOUTH. THIS ESTABLISHMENT IS UNDER COURT ORDER TO CONNECT TO CITY SEWER SO THE CITY WILL EXPECT CONSTRUCTION TO PROCEED IMMEDIATELY AFTER THE CONTRACT IS AWARDED.

CAUTION
UNDERGROUND
UTILITIES

PLAN
NOTE BOOK
No. 720

PROFILE
NOTE BOOK
No.

105
100
95
90
85

Sta 0+00
Exist. M.H. (No Stub South)
Begin 8" Pipe

Sta 1+07
Const. Std. M.H.
Type 'A' or 'C'

Sta 1+61
Const. Std. M.H.
Type 'A' or 'C'
Install 4" Stub South
End Project

Exist. Manhole

Natural Ground

Flo (Sta 0+00) 90.00
Flo 90.85
Flo 91.17
Flo (Sta 1+61) 90.91

181 Lin Ft of 8" Clay Pipe @ 1% Grade
Alt. 8" ABS Composite Pipe

0 1 2

PLATE 1, PLAN-PROFILE
KEUFFEL & ESSER CO
48 7024 MADE IN U.S.A.

As Built 10-26-78

LAT 60 WAR INDUSTRIES SEWER
CITY OF WICHITA, KS.
R. W. LINN CITY ENGINEER
Project No. 468-76-245-80540-000-000-001

Ie 2 3 8