B.M. 120.16 R.R. Spike N.S. P.P. at N.E. corner Julia and Toft.

B.M. 118.35 #60 Spike in washer S.E. face P.P. of S.E. corner Lot 6, Blk. A, Garst Gardens.

Plan Scale 1" = 40'
Profile Scale 1" = 40' Horz.
1" = 4' Vert.

Garst Street

Julia Street

Toft Ave.

Hendryx Ave.

Kellogg Drive

Garst Gardens

Byron Stout Addn.
Lot 1, Blk. 1

10' Perm. Easement (Typical)

16' Perm. Easement

40' Texas Empire Pipeline Easement

Pipeline

Sta. 0+00.0 Exist. M.H. Exist. 8"-15" Stub So.

Sta. 2+40.0 Const. Std. M.H. Type "A"

Sta. 4+80.0 Const. Std. M.H. Type "A"

Sta. 7+16.0 Const. Std. M.H. Type "A"

Sta. 10+20.0 Const. Std. M.H. Type "A"

match line Sta. 8+90.0

match line Sta. 8+30.0

GARST ST.

HENDRYX

NOTE:
CONTRACTOR TO CO-ORDINATE THIS PROJECT WITH CONTRACTOR ON MAIN 4, S.W. INTERCEPTOR

Natural ground

Proposed E. cb Julia St.
Proposed W. cb Garst St.

Proposed S. cb Hendryx Ave.

Set top M.H. @ 118.00

8" Clay Pipe @ 0.20 %

1005 lin. ft. of 8" V.C.P. @ 0.20 % grade.

LAT 30, S.W. INTERCEPTOR SEWER
CITY OF WICHITA, KANSAS
R. W. LINN — CITY ENGINEER
197 PROJECT NO. DBKL 5 69057

14 3 5 (e)