B.M. 120.16 R.R. Spike N.S. P.P. at N.E. corner Julia and Toft.

B.M. 118.35 #60 Spike in washer S.E. Post P.P. at S.E. corner Lot 6, Blk. A, Garst Gardens.

Garst Street

Julia Street

Toft Ave.

Hendryx Ave.

Garst Gardens

Byron Stout Addn. Lot 1, Blk. 1

Kellogg Drive

GARST ST.

HENDRYX AVE.

Sta. 7+30.0 Exist. M.H. Exist. 8"-15" Stub So.

Exist. 18" S.S. (Main Conc. Encased)

10' Perm. Easement (Typical)

10' Perm. Easement

16' Perm. Easement

Sta. 2+40.0 Const. Std. M.H. Type "A"

Sta. 4+80.0 Const. Std. M.H. Type "A"

match line Sta. 8+30.0

40' Texas Empire Pipeline Easement

Sta. 7+16.0 Const. Std. M.H. Type "A"

Sta. 10+20.0 Const. Std. M.H. Type "A"

60' Typical

NOTE :
CONTRACTOR TO CO-ORDINATE THIS PROJECT WITH CONTRACTOR ON MAIN 4, S.W. INTERCEPTOR

Sta. 0+00.0 Exist. M.H. Exist. 8"-15" Stub So.

Sta. 2+40.0 Const. Std. M.H. Type "A"

Sta. 4+80.0 Const. Std. M.H. Type "A"

Sta. 7+16.0 Const. Std. M.H. Type "A"

Sta. 10+20.0 Const. Std. M.H. Type "A"

Building floor elev. 1819

Natural ground

Proposed E. cb Julia St.

Proposed W. cb Garst St.

Proposed S. cb Hendryx Ave.

Set top M.H. @ 118.00

8" Clay Pipe @ 0.20%

8" Std. Pipe @ 0.20%

1005 lin. ft. of 8" V.C.P. @ 0.20% grade.

LAT. 30, S.W. INTERCEPTOR SEWER
CITY OF WICHITA, KANSAS
R. W. LINN — CITY ENGINEER
197 PROJECT NO. DBKL 5 69057