B. M. 142.43 S.E. cor. conc. porch 513 Floyd St.

T. B. M. 140.89 N.E. cor. conc. dr. 513 Floyd St.

Plan Scale 1" = 40'
Profile Scale 1" = 10' Horz.
1" = 5' Vert.

Caution: 2" intermediate-low pressure gas line with Gas Service Co. Prior to excavation. Call Tele 268-7511, ext. 274.

Sta. 0+00 ~ Existing 8" Clay Pipe Begin 8" Clay Pipe

Sta. 0+44 ~ Construct Std. Type "A" M.H. # 8" Stub N.E.

Contractor to replace gravel surface 9' wide. To be paid at bid price of Tons Road Gravel

Caution: 8" Water Main with 3 Ft. Coverage

Note to Contractor: Do not remove this tree! Work around.

Sta. 3+72 ~ Construct Line #1 Std. Type "A" M.H.

Sta. 5+68 ~ Construct Std. Type "A" M.H.

Sta. 7+68 ~ Construct Std. Type "A" M.H.

Sta. 9+38 ~ End 8" Clay Pipe Construct Std. Type "A" M.H.

Sta. 2+04 Line #1 Sta. 0+00 Line #2 Construct Std. Type "A" M.H. # 8" Stub NE

Sta. 0+00 Line #2 Existing M.H. ~ Begin 8" Clay Pipe

Sta. 2+00 ~ End 8" Clay Pipe Plug Pipe

Caution: 8" intermediate-low pressure gas line with 3" coverage. See note above.

Caution: 8" water main with 3' coverage.

Sta. 0+44 ~ Construct Std. Type "A" M.H. # 8" Stub N.E.

Sta. 0+00 Line #2 Construct Std. Type "A" M.H. # 8" Stub NE

Sta. 3+72 ~ Construct Std. Type "A" M.H.

Sta. 5+68 ~ Construct Std. Type "A" M.H.

Sta. 7+68 ~ Construct Std. Type "A" M.H.

Sta. 9+38 ~ End 8" Clay Pipe Construct Std. Type "A" M.H.

Floyd Bailey 3rd Addn.

B.E. Mesker 210 Pattie

B.E. Mesker

Ed. Cody Construction 11828 Taft

Ed. Cody Construction Co. 11828 Taft

Willis H. Cook 509 Floyd

FLOYD ST.

SOCORRA DRIVE

EVERGREEN LANE

TURQUOISE LANE

P.C.K. TATE

8" Stub

Natural Ground

N.L. Floyd T.C.

S.L. Socorra T.C.

8" Crossline #2 ~ Sta. 2+04 Line #1 Existing M.H. ~ Begin 8" Clay Pipe

200.0 L.F. 8" C.P. @ 0.15% Grade

LINE #2

768.0 L.F. 8" Clay Pipe @ 0.15% Grade

LINE #1

170.0 L.F. 8" Clay Pipe @ 0.30% Grade

Flo 134.16 Flo 134.31 Flo 134.46 Flo 134.47

Flo 133.78 Flo 133.85 Flo 133.93 Flo 134.18 Flo out 134.16 Flo in 134.33 Flo 134.44 Flo 134.48 Flo 134.63 Flo 134.73 Flo 134.78 Flo 134.93

Flo 135.03 Flo 135.13 Flo 135.43 Flo 135.54

0 1 2 0 1 2 3 4 5 6 7 8 9

As Built Per Plan K-111

LAT. 58, S. W. INTERCEPTOR SEWER
CITY OF WICHITA, KANSAS
R. W. LINN — CITY ENGINEER
1973 PROJECT NO. DBKL 573021

LINN W. LAURICK LICENSED 6363 KANSAS PROFESSIONAL ENGINEER