Plan Scale: 1" = 40'
Profile Scale: 1" = 40' Horiz.
1" = 5' Vert.

STONY POINT

WESTLINK VILLAGE 14th ADDN.

STREET

17TH

SKYVIEW

Sta 0+00 Remove Plug Const. Std. M.H. Type "A" or "C"

Sta 0+58½ Const. Std. M.H. Type "A" or "C"

Sta 0+62 Const. Std. M.H. Type "A" or "C"

Sta 1+11½ Const. Std. M.H. Type "A" or "C"

Sta 1+80 Const. Std. M.H. Type "A" or "C"

Sta 2+77½ Const. Std. M.H. Type "A" or "C"

Sta 3+30 Const. Std. M.H. Type "A" or "C"

Sta 3+80 Const. Std. M.H. Type "A" or "C"

Sta 4+80 Const. Std. M.H. Type "A" or "C"

Sta 10+72 Plug Pipe End Construction

℄ 20' Utility Esmt.

℄ 10' Utility Esmt.

Proposed 8" AC Water Line

Proposed E.C6 Stony Point

Proposed W.C6 Skyview

Top M.H. elev. 159.07

Top M.H. elev. 158.98

Alternate 8" A.B.S. Composite Pipe

As built 9-7-78

B.M. 157.04 RR. Spike North face Power Pole approx. 200' South and 100' west of NW. corner Nantucket and Lark. (℄ RR N. of Maize road on 13th)

B.M. 163.92 Top Metal post approx. 100' west and 120' N. of NW. corner of 17th and Skyview.

LAT 93 SOUTHWEST INTERCEPTOR

CITY OF WICHITA, KANSAS

R.W. LINN CITY ENGINEER

PROJECT NUMBER: 468-76-245-80353-000-000-001