NOTE: Construction to start within 7 days after awarding of contract. Construction time 30 days.

NOTE: MANHOLE AT STATION 0 + 00 IS APPROXIMATELY 1,187 FEET SOUTH OF SOUTH LINE OF UNIVERSITY AVENUE.

BENEFIT DISTRICT - PART OF LOT 1, RIDGE PLAZA 3RD ADDITION AS DESCRIBED IN RESOLUTION.

Scale: 1"=50'

℄ HOLLAND STREET

Existing 10" Main 4

M.H. F.H. M.H.

B.M.

5" Conc.

70' R/W

40' B/B

7.0' R/W

Conc.

P.P.

LATERAL "H"

Elec. Box

Telephone Riser

4' Sidewalk

4'-0" Back Curb

Sta. 0+00 Constr.
Std. Manhole Type "A"
Manhole H-0

Remove & Replace Conc. drives as per spec.

Sta. 3+13 Constr.
Std. Manhole Type "A"
Manhole H-1

LOOP ROAD (Future)

70' R/W

Sta. 7+41 Constr.
Std. Manhole Type "A"
w/ 8" Stub East & North
Manhole H-2, Connect to Exist. 8" Sewer

Existing 10" Main

MOTEL SITE

CLUB SITE

B.M. - Chiseled "a" west curb Holland at Loop Rd. Elev. 139.52

OFFICE PARK SITE

Manhole H-0

Manhole H-1

Manhole H-2

Existing Ground

140

135

130

125

NOTE: Laythrough Manhole And Plug For Future Extension

Plug

375 L.F. of 8" V.C.P. @ 0.4%

375 L.F. of 8" V.C.P. @ 0.4%

+50 / 1+00.00

+73 - 128.50

128.80 - 0.4%

127.00 I.E.

127.40

127.80

128.20

128.60

129.00

129.40

129.80

R.W. LINN
CITY ENGINEER
3E34

GARY R. MEYER
LICENSED
17489
KANSAS
PROFESSIONAL ENGINEER

POE & ASSOCIATES OF KANSAS, INC.
CONSULTING ENGINEERS

LAT 30, MAIN 4, SW INTERCEPTOR
CITY OF WICHITA
R.W. LINN - CITY ENGINEER

CITY PROJECT NO. 468-76-245-80-01-000-000-001