

Sta. 0+10.8' Lt. Remove  
Exist. Manhole. Plug  
Exist. Sewer Lines  
N, S & N.W.

Sta. 0+00. Connect to  
Exist. Manhole. Reshape  
Invert & Plug Ex. 8"  
Sewer S.E.


Exist. 8" San. Sewer to  
be abandoned. Sewer  
to be removed where  
required to install  
new sewer. Exist.  
sewer to be plugged  
on both ends

Scale: Hor. 1"=20'  
Ver. 1"=5'

B.M. Top iron in thimble  
& Laura & Lewis  
E.I. 107.75


Sta. 3+07. Const. Std.  
Type "A" Manhole  
Remove Exist. Manhole

NOTE: CONTRACTOR'S METHOD FOR HANDLING SEWAGE FLOWS DURING CONSTRUCTION OF THIS PROJECT SHALL BE APPROVED BY THE ENGINEER. CONTRACTOR WILL BE REQUIRED TO OBTAIN PERMITS FROM PUBLIC WORKS ADMINISTRATION BEFORE RECONNECTING BUILDING SERVICE LINES. PERMIT FEE WILL BE WAIVED. BID ITEM FOR SERVICE CONNECTIONS SHALL COVER ALL COSTS FOR FURNISHING AND INSTALLING SADDLE INCLUDING TAPPING FEE. PIPE TAPS ARE TO BE MADE BY CITY MAINTENANCE DEPARTMENT PERSONNEL UNLESS APPROVED OTHERWISE BY THE ENGINEER. ONLY ACTIVE BUILDING SANITARY SEWER LINES ARE TO BE RECONNECTED TO THE NEW SEWER. CONTRACTOR SHALL VERIFY WHICH LINES ARE ACTIVE. EVERY BUILDING SEWER RECONNECTED TO THE NEW SEWER SHALL BE TRAPPED. CLEAN OUTS SHALL BE INSTALLED WITH THE TRAPS. TRAPS AND CLEAN OUTS SHALL BE CLASS 52 CAST IRON PIPE AND WILL BE PAID FOR AT THE UNIT PRICE BID PER LINEAL FOOT OF CAST IRON PIPE. LOCATION OF TRAPS AND CLEAN OUTS SHALL BE AS APPROVED BY THE ENGINEER. THE ALLEY PAVING PLAN SHEET HAS BEEN INCLUDED IN THIS PLAN TO FACILITATE SETTING UP OF CLEAN OUTS TO MATCH PAVEMENT ELEVATIONS WHERE IT MAY BE NECESSARY TO INSTALL CLEAN OUTS IN THE ALLEY RIGHT-OF-WAY. CONTRACTOR SHALL GIVE ALL PROPERTY OWNERS AND TENANTS AFFECTED BY THE CONSTRUCTION OF THIS PROJECT A MINIMUM OF 24 HOURS ADVANCE NOTICE PRIOR TO START OF CONSTRUCTION.



Sta. 0+00. Connect  
to Exist. Manhole  
Reshape Invert

Sta. 3+07. Const. Std.  
Type "A" Manhole  
Top E. 106.70



RECONSTRUCTION OF LAT. 10, S.S. 20 IN  
ALLEY BETWEEN LAURA & PATTIE FROM  
N.L. LEWIS TO N.L. RICH'S SUB.  
CITY OF WICHITA, KANSAS  
R.W. LINN CITY ENGINEER  
JULY, 1979  
PROJ. NO. 542 80 245 80024 000 000 001

Elevations: 102.85, 102.85, 103.05, 103.15, 103.25, 103.35, 103.36

Handwritten notes and numbers: 14, 2, 5, 11