CT. PAUL AVE.

ST

Sullivan 31.23

20' Temp. Easm't.

Station 3+15

Sullivan 101.25

20' Temp. Easm't.

PARK VISTA ADDITION

17 15 14 13 12 11 10 9 8

TENTH ST.

Book K-36

Sewer Ex. 1941
Sewer Ex. 1941
Sewer Ex. 1941
Sewer Ex. 1941

NINTH

Station 0+33

Station 0+00

Sta. Sewer Ex.

EDWARDS

B.M. 119.28 DOUBLE SPIKE IN SIDE POLE #1000 N.E. COR. 3RD & EDWARDS.

PLAN SCALE 1"=40'
PROFILE SCALE 1"=40' HOR. 1"=4' VERTICAL.

Station 0+00 Existing M.H.

Station 0+33 Standard M.H.

Station 3+15 Standard M.H.

Station 7+00 Standard M.H.

Station 101+25 Standard M.H.

St. Paul Co.

117.9 Low Ch. @ NE. Cor. Lot 8

Natural Ground

Sand Fill Sta. 0+00 To 0+10

108.13 F.G.

108.00 In

30"

104.93 Out 30"

102.5 Lin. Ft. 8" V.C.P. @ .4% Grade

109.60 In
109.50 Out
103.50 - 8" Stub W.

F.G. 110.90

112.20 Out

100.00 100.30 100.60 100.90 101.20 101.50 101.80 102.10 102.40 102.70 103.00 103.30 103.60 103.90 104.20 104.50 104.80 105.10 105.40 105.70 106.00 106.30 106.60 106.90 107.20 107.50 107.80 108.10 108.40 108.70 109.00 109.30 109.60 109.90 110.20 110.50 110.80 111.10 111.40 111.70 112.00 112.30 112.60 112.90 113.20 113.50 113.80 114.10

1025 Lin. Ft. 8" V.C.P. @ .4% Grade

375 Lin. Ft. 6" Plain Concrete Encasement

0 1 2 3 4 5 6 7 8

LATERAL 43 SANITARY SEWER 32
CITY OF WICHITA, KANSAS
B.F. SMITH CITY ENGINEER
PROJ. NO. C27-11 DATE- NOV. 1957