S. M. 94.31 "P" in Pkg. S. of 34th St. east & St. Clair.

Plan: Scale 1" = 40'
Profile Scale 1" = 4 Vert.
1" = 40' Horiz.

35TH ST. SO.

JOSEPH E. HALL ADDITION

HATCHER - GOMEZ ADDITION

CHURCH BLDG.

NOTE: All exist. buildings have to be removed.

Sta. 11+30.0 Const. Std. M.H. Type "A"

Sta. 7+60.0 Const. Std. M.H. Type "A"

Sta. 3+42.8 Const. Std. M.H. Type "A"

Sta. 0+00.0 Line No. 2 St.

Sta. 0+16.8 Const. Std. M.H. Type "A"

Sta. 0+10.0 Exist. 8" Stub east

LINE NO. 1

LINE NO. 2

EVERETT AVE.

ST. CLAIR AVE.

MERIDIAN AVE.

34TH ST. SO.

Exist. M.H. Flo 88.38

Exist. M.H. Flo 87.50

Exist. Pavement

Foundations for Duplex

Natural ground

Exist. W. cb St. Clair Ave.

N. Rt. 35th St. So.

Proposed S. cb 34th St. So.

North property line of 35th St. So.

765 lin. ft. of 8" Clay Pipe @ 0.20% grade.

130 lin. ft. of 8" Clay Pipe @ 0.30% grade.

8" Clay Pipe @ 0.20 %

8" Clay Pipe @ 0.30 %

89.27 Flo out 89.37 Flo in

89.57 Flo out 89.67 Flo in

89.67

89.87

90.07

90.26 Flo out 90.36 Flo in

90.37

90.57

90.69 Flo

90.77

90.97

91.11 Flo

90.26 Flo out 90.36 Flo in

90.56

90.65 Flo

95

90

85

0 1 2 3 4 5 6 7

0 1

Surveyed by D. L. N. Mr. No. D.C.K. #3
Plotted by
Checked by

436

LAT. 30, SUBMAIN 3, S. S. NO. 22

CITY OF WICHITA, KANSAS

B. E. SMITH - CITY ENGINEER

JAN. 1971 PROJECT NO. 029-49