B.M. 168.54 Standard S.W. Corner Douglas & Oliver.

Sta. 0+00 Exist. Manhole.

Exist. 8" V.C.P.

Dellrose Avenue

Sta. 0+38 Constr. Std. Brick Manhole, Type A. Install 4" Stub West.

American Savings Drive-Up Facility

Exist. M.H. Flow = 160.94

Exist. 8" V.C.P.

Exist. 8" V.C.P.

East Douglas Avenue

Note: All lines of removal to be sawed. All walk and pavement removed shall be replaced.

Plan Scale 1" = 40'
Profile Scale Horz. 1" = 40'
Vert. 1" = 4'

Sta. 0+00 Exist. Manhole.

Sta. 0+38 Constr. Std. Brick Manhole, Type A. Install 4" Stub West.

Exist. Ground

Sand Fill or Flush

38 L.F. 8" V.C.P.

0+00 Flow Out = 157.85
0+00 Flow In = 161.50

0+38 Flow = 162.00

170

160

AMERICAN SAVINGS
DRIVE-UP FACILITY
SEWER
CITY OF WICHITA, KANSAS
B. E. SMITH, CITY ENGINEER
PRIVATE CONTRACT
DATE: Oct. 1968

Survey by D.C.S. Book D.C.S. # 2
Plan Checked by

25TH ST. SO.

LAZY R 2. ADDITION

BIG LEAGUE DUGOUT RESTAURANT

SENECA ST.

Sta. 0+00.0 Exist. M.H.

NOTE: Replace A.C. Surface 4"

Asphalt Surface

Sta. 3+20.0 Const. Std. M.H. Type "A" Install Stub W.

Prop. Iron

Exist. 8" V.C.P.

Cone curbing

5.6' Wood Fence

N

Plan Scale 1" = 40'
Profile Scale 1" = 40' Horz.
1" = 4' Vert.

B. M. 102.33 "K" in Mid Kansas S. side walk section of drive to house No. 930 W. 25Th S.

Asphalt Surface

Natural Ground

S. Rim No. 1 = 101.47

8" V.C.P. @ 0.30 ft.

Sta. 0+00.0 Exist. M.H.

Sta. 3+20.0 Const. Std. M.H. Type "A" Install Stub W.

95.82 F/O Exist. M.H.
95.92 F/O Const. M.H.

96.36

96.76

97.12

97.20 F/O

380 lin. ft. of 8" V.C.P. at 0.30% grade.

100

90

0 1 2 3

LAT. 17, SUBMAIN 4, S. S. NO. 22
CITY OF WICHITA, KANSAS
B. E. SMITH CITY ENGINEER
APRIL 1969 PROJECT NO. C 29-15

8 12 3 (S)