NOTES:
REPLACE FENCES, SET
2 IRONS PER LOT.

ANNA ST.

ELM ST.

MURDOCK AVE.

BAEHR ST.

GROVES ADDITION

GROVE'S SECOND ADDITION

Scale 1"=40'

B.M. 123.04 SW COR CONC. STEP NO# 800 N. BAEHR

PLAN SCALE 1"=40'
PROFILE SCALE 1"=40' HOR, 1"=4 VERTICAL

560 LIN. FT. 8" VCP @ 0.40% GRADE

LATERAL 145 SUB. 5 SAN. SEWER 22
CITY OF WICHITA, KANSAS
B.E. SMITH CITY ENGINEER
PROJ. NO. C20-14 DATE- MAY 1940