EISENHOWER AVE.

CENTRAL AVE.

BOYD AVE.

ELM ST.

WEST CENTRAL GARDENS

Leonard L. Beverly 1124 N. 38th St. No.

Mattie Humphrey 318 Nora

Charles W. Nye 1228 N. Custer

Isaac W. Benson 1134 N. St. Francis

Leader P. Rollin 748 Boyd

Joel L. Carroll 734 Boyd

Lee E. Hansen 720 Boyd

George Hudson 1154 N. St. Francis

Existing 8" VCP

STATION 0+00

STATION 4+00

STATION 8+00

Elm Hedge

NOTES:
REPLACE FENCES, SET 2 WYES PER LOT.

SCALE 1"=40' N

PLAN SCALE 1"=40'
PROFILE SCALE 1"=40' HOR, 1"=4' VERTICAL

B.M. 123.30 HEAD BOLT WS HLP NS 6th 136' W OF EISENHOWER

EXISTING M.H.

STATION 0+00

STATION 4+00

STATION 8+00

NATURAL GROUND

IDENTICAL CURBS

40' SANITARY FILL

600 LIN. FT. 8" VCP @ 0.40% GRADE

115.22 IN EXIST 8" STUB
115.22 FLD. M.H.

116.42 FLD

117.62 OUT

600 LIN. FT. 8" VCP @ 0.40% GRADE

LATERAL 146 SUB. 3 SAN. SEWER 22
CITY OF WICHITA, KANSAS
B.E. SMITH CITY ENGINEER
PROJ. NO. C20-16 DATE: May 1940

8 2 4 10