NOTE: Sheds are to be moved off of permanent easement. Sheds are to be reset on foundations equal to original foundation.

Sta. 0+00.0 Exist. M. H.

Sta. ~~2+62.3~~ 2+63.9 Const. Std. M. H. Type "A" or "C"

Sta. ~~3+11.4~~ 3+14 Const. Std. M. H. Type "A" or "C"

Sta. ~~6+00.0~~ 6+81.9 Const. Std. M. H. Type "A" or "C"

Sta. ~~8+00.0~~ 8+81.8 Const. Std. M. H. Type "A" or "C" Install 4" Stub East & West

NOTE: Dashed lines indicate proposed SMITH'S PARKWILDE ADDITION.

Proposed NEVADA ST.

PARKWILDE

ADDITION

20' Temp. Easement

20' Temp. Const. Easement

Permanent Easement

16' Permanent Easement

FIRST ST.

DOUGLAS AVE.

Existing 8" Iron Sewer

Existing 10' Easement

Ethel Mosley 218 N. Tracy

Propose vacating FIRST ST.

B. M. 120.23 "M" in Mueller Fire Hyd. S. E. Cor. Tracy & Douglas.

TRACY ST.

Plan Scale 1"=40'
Profile Scale 1"=40' Hor.
1"=5' Vert.

S. Rim M.H. = 118.17

Proposed E. cb Tracy St.

EXIST. GROUND

Top Exist. Curb on Tracy St

Exist. ground

Exist. F/o = 111.61
8" F/o in 111.61

111.81 — 112.01 — 112.13 F/o out 112.23 F/o in — 112.31 — F/o out 112.43 F/o in — 112.41 — 112.81 — 113.01 F/o — 113.21 — 113.41 — 113.57 F/o

880 Lin. Ft. of 8" Clay Pipe @ 0.20 % grade.

0 1 2 3 4 5 6 7 8

DONALD E. SCHNEIDER LICENSED 6311 KANSAS PROFESSIONAL ENGINEER

As Built 9-4-75

LAT. 208, MAIN 5, S. S. #22
CITY OF WICHITA, KANSAS
R. W. LINN, CITY ENGINEER
PROJ. NO. DBKL570062
DATE: