RICHMOND ST.

N

REPLAT OF PART OF LOTS 4, 5, & 6 IN

NOTE: Save these trees.

Janeva I. Snyder 4360 N. Richmond

James M. Davis 2830 N. Richmond

BAYS

Paul E. Bays 2801 Halstead

LINE NO. 1

LINE NO. 1-A Wayne E. Snyder

BULLINGER GARDENS

SUBDIVISION

Paul E. Bays 2801 Halstead

Paul E. Bays

NOTE: Replace fences.

27TH ST. NO.

RICHMOND ST.

HALSTEAD

MERIDIAN AVE.

Survey by C.K. Plan by C.K. Checked by

Plan Scale 1" = 40'
Profile Scale 1" = 40' Horz.
1" = 4' Vert.

Sta. 0+32.2 Existing M.H. with 9" S.L.B. N.E.

Sta. 0+52.0 Const. Std. M.H.

Sta. 1+33.0 Const. Std. M.H.

Sta. 2+39.0 Const. Std. M.H. Sta. 0+00 Line 1-A

Sta. 3+19.0 Const. Std. M.H.

Sta. 0+00.0 Line No. 1-A = Sta. 2+39.0 Line No. 1.

Sta. 0+40.2 Const. Std. M.H.

Sta. 0+00.0 Existing with 8" Stub N.E.

Prop. W. cb 27th St. N.

Natural ground

Prop. W. cb Halstead St.

Prop. S. cb Richmond

LINE NO. 1

Sand fill or flush

8" V.C.P. @ 0.4 %

137.93 N. Rim Elev.

130

120

120.50 Flo in

121.01 Flo out 121.41 Flo in

121.30

121.70 Flo

121.86 Flo 121.96 Flo

122.64 Flo

390 Lin. Ft. 8" V.C.P. @ 0.4 % grade

0 1 2 3 4

LINE NO. 1-A

0.4 %

8" V.C.P.

40 Lin. Ft. 8" V.C.P. @ 0.4% grade

121.86 Flo in

122.02 Flo out

0 1

LAT. 15, SUBMAIN 17, S. S. NO. 22

CITY OF WICHITA, KANSAS

B. E. SMITH CITY ENGINEER

JUNE 1964, PROJECT NO. C23-46