B.M. 145.70 "X" cut in top E. end N. hubguard R.C.B., 100' E. of Westlink on Central.

Plant Fixtures

CENTRAL AVE.

Scale 1"=40'

ROLLING HILLS 8th ADDN. 1 2

AVE.

162.65' 162.5' 140' 140' 292' 8' 8' 163.21' 172.74' 332.65' 5' 10' Esmt. 320' 404.35'

Iron Iron

Sta. 0+27± Const. Std. M.H. Type "A"

Sta. 2+60 Const. Std M.H. Type "A"

Sta. 0+00 Exist. M.H. Begin Const.

WESTLINK

Lot 1

ROLLING HILLS 7th ADDN.

Scale 1"=40' Hors. 1"=4' Vert.

Sta. 0+00 Exist. M.H.

Sta. 0+27± Const. Std. M.H. Type "A"

Sta. 2+60 Const. Std. M.H. Type "A"

Natural Ground

Top of Proposed W.Cs of Westlink Ave

145 140 135 130

+0.4% 8" VCP +0.4%

153.30 Flo Out 133.70 Flo In 133.81 Flo In 134.00 134.20 134.40 134.60 134.84 Flo Out

260 Lin. Ft. 8" VCP @ 0.4% Gr.

0 1 2

LAT. 28, WESTLINK SEW.
CITY OF WICHITA, KANSAS
B.E. SMITH, CITY ENGINEER
PROJ. NO. C 27-40 DATE

B.M. 130.18 #60 Spike E. Side Transformer Pole West Side McDonnall Addn. @ 33rd Street.

Clarence Ave.

Scale 1"=40'

Survey Young & Schneider Exc. Contractor

85' 82' 81.82' 85' 30' 30'

4 3 2 1 Addn.

16" Tree 190' 10' Drainage Easmt 170' Fence

Sta. 1+60 Const. Std. Brick Manhole Type A.

Sta. 3+34 Constr. Std. Brick Manhole Type A With 8" Stub North.

16' Easement

Exist. 8" V.C.P. @ 0.15%

95' 82' 81.91' 85' 90' 90' 153.91' 8'

℄ 16' Easmt.

Sta. 0+00 Exist. Brick Manhole. Begin Project.

Block 2 6

5 7

McDonnall

Clothes Line Post 8" Tree House 6" Tree

5' Utility Easmt 170' 190'

154' 90' 90'

Fourth Street

Charles Ave.

Plan Scale 1"=40'
Profile Scale Horz. 1"=40' Vert. 1"=4'

Top of Curb Charles Ave.
Top of Curb Clarence Ave.

Exist. Ground

130 120

160 L.F. 8" V.C.P. @ 0.15% 114 L.F. 8" V.C.P. @ 0.15%

0+00 Exist. Manhole Flow = 125.92

1+03 Flow = 126.07

1+60 Constr. Manhole Flow = 126.16

2+00 Flow = 126.22

3+00 Flow = 126.37

3+34 Constr. Manhole Flow = 121.92

JAMES H. TAYLOR 2012 KANSAS REGISTERED LAND SURVEYOR

B. E. SMITH 436 REGISTERED ENGINEER KANSAS

LAT. 49, SUB. 17, S. S. 22
CITY OF WICHITA, KANSAS
B. E. SMITH, CITY ENGINEER
PROJ. NO. C 27-53
DATE: MARCH 1968

S 22 E 1